




4. CORRECTIVE PRUNE TO RETAIN NATURAL FORM OF TREE AS DIRECTED BY THE LANDSCAPE ARCHITECT, INCLUDING REMOVAL OF DEAD, BROKEN, OR CROSSING BRANCHES. DO NOT REMOVE MORE THAN 20% OF LIVE CANOPY.

3. POSITION CROWN OF ROOT BALL 75mm ABOVE FINISHED GRADE TO ALLOW FOR SETTLING.


5. FOR TREES PLANTED WITHIN PLANTING OR SHRUB BEDS, DELETE SAUCER AROUND BASE OF TREE.

2. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.

6. NO TREE PITS SHALL BE LEFT OPEN OVERNIGHT.



NTS



SHRUB PLANTING NTS CONTRACT DRAWINGS <u>NOTES</u>

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE 1. ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE INDICATED. RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE CONSULTANT BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED. ENVISION-TATHAM CLAIMS COPYRIGHT TO THIS DOCUMENT WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE LANDSCAPE ARCHITECT WITHOUT THE EXPRESS CONSENT OF ENVISION-TATHAM

APR. 12/18 REVISED AS PER CLIENT COMMENTS REVISIONS DATE INITIAL

APPROVED

SCENIC CAVES OVERFLOW PARKING AREA TOWN OF THE BLUE MOUNTAINS

LANDSCAPE DETAILS

SCALE: AS SHOWN JOB NO. ET118005-1 DESIGN: AB CHECKED: AB LD-1 DATE: APRIL 3, 2018 DRAWN: AL

GENERAL NOTES

SPECIFICATIONS.

WHERE SPECIFIED OTHERWISE.

CHEMICALS, OR APPROVED EQUAL.

PRIOR TO INSTALLATION.

PLASTIC TREE GUARD.

WARRANTY PERIOD.

1. SUPPLY AND INSTALL TREES, SHRUBS AND GROUNDCOVERS IN

2. PLANT MATERIAL SHALL BE IN ACCORDANCE WITH THE CANADIAN

LANDSCAPE STANDARD (LATEST EDITION), PUBLISHED BY THE

CANADIAN NURSERY LANDSCAPE ASSOCIATION AND THE CANADIAN SOCIETY OF LANDSCAPE ARCHITECTS, EXCEPT

3. ALL PLANTS SHALL BE SUPPLIED AS SPECIFIED IN THE 'PLANT

LIST'. SUBSTITUTIONS WILL NOT BE ACCEPTED UNLESS

APPROVED IN WRITING BY THE LANDSCAPE ARCHITECT.

5. MULCH TO BE SHREDDED CEDAR BARK FREE OF DYES AND

6. PLANTING SOIL MIXTURE SHALL BE TWO PARTS SCREENED

TOPSOIL TO ONE PART SCREENED COMPOST WITH BONEMEAL

APPLIED AT A RATE OF 0.6KG PER CUBIC METRE, AS SPECIFIED.

MIXTURE, AS SPECIFIED, FOR APPROVAL PRIOR TO COMMENCING

CONTRACTOR SHALL PROVIDE SOURCE AND SAMPLE OF SOIL

7. TREE STAKES TO BE 1800mm LONG HEAVY DUTY GAUGE T-BARS.

SYSTEMS THAT REMAIN FLEXIBLE DURING WINTER MONTHS.

9. TRUNK PROTECTION TO BE 100mm DIA. HDPE PIPE, 500mm LONG

10. STAKES AND TIES SHALL BE REMOVED 1 YEAR AFTER PLANTING.

11. TRUNK PROTECTION SHALL BE REMOVED AT COMPLETION OF

12. CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND OFFSITE

CONSTRUCTION AND TREE PIT EXCAVATION.

DISPOSAL OF EXCAVATED MATERIAL FROM PLANTING BED

50mm WIDE BURLAP STRIPS LOOPED IN A LOOSE FIGURE 8 AND

8. TIES SHALL BE WOVEN POLYPROPYLENE PROPRIETARY TIE

SECURED WITH WIRE TIES ARE ALSO ACCEPTABLE.

OR TO LOWEST BRANCH, EXCEPT IN SWM PONDS AND

NATURALIZATION AREAS WHERE IT IS TO BE WHITE SPIRAL

4. ALL MATERIALS TO BE APPROVED BY LANDSCAPE ARCHITECT

ACCORDANCE WITH THE APPLICABLE DETAILS AND

1.0 PLANTING