


MANORWOOD HOMES - SECOND NATURE

TOWN OF THE BLUE MOUNTAINS



KEY PLAN



The Consultant shall provide a Communications Plan to notify the Town and Area Residents of significant Construction activities to the satisfaction of the Town.

At a minimum the Plan should provide:

- Installation of a Project Notification Sign, 1.2 m x 2.4 m minimum, to Town template, at each construction access to the Lands and visually obvious to the public, at least two (2) weeks before the construction start date, and maintained for full duration of construction.
- Notification of the construction project to property owners as deemed appropriate in consultation with Development Engineering via hand/mail delivery.
- Schedules of intended site activities updated routinely. (typically, weekly to bi-weekly).
- A minimum of two (2) weeks' notice following Town approval and prior to commencement of:
 - o Significant site activities such as site alteration works e.g. tree clearing & grubbing, commencement of site servicing/grading, placement of asphalt, concrete curbs and sidewalk, and landscaping.
 - o Off-site works on Town Owned Lands/Roads following receipt of a Municipal Land Use Permit (MLUP).



PHASE 2 BLOCK - 152
Contract No. : 117227
4TH SUBMISSION
DATE: APRIL 27, 2020

MANORWOOD HOMES - SECOND NATURE

TOWN OF THE BLUE MOUNTAINS

INDEX

CIVIL

Dwg.	Description
TP-1	TITLE PAGE
IN-1	INDEX AND LEGEND
SD-1	STORM DRAINAGE PLAN
SD-2	STORM DESIGN SHEET
WD-1	WATER DISTRIBUTION PLAN
ES-1	EROSION AND SEDIMENT CONTROL PLAN
SS-1	SITE SERVICING PLAN
SG-1	SITE GRADING PLAN
SG-2	SITE GRADING PLAN
SG-3	SITE GRADING AND DETAILS PLAN
PP-1	PLAN AND PROFILE STREET A STA. 0+995 TO STA. 1+130
PP-2	PLAN AND PROFILE STREET A STA. 1+130 TO STA. 1+174 PLAN AND PROFILE SERVICE CORRIDOR STA. 3+992 TO STA. 4+051
PP-3	PLAN AND PROFILE STREET B STA. 1+995 TO STA. 2+140
PP-4	PLAN AND PROFILE STREET B STA. 2+140 TO STA. 2+258 PLAN AND PROFILE SERVICE CORRIDOR STA. 4+995 TO STA. 5+054
PP-5	PLAN AND PROFILE STREET C STA. 2+968 TO STA. 3+029
PM-1	PAVEMENT MARKING AND SIGNAGE PLAN
CUP-1	COMPOSITE UTILITY PLAN
DE-1	DETAILS & NOTES
DE-2	DETAILS

LANDSCAPE


Dwg.	Description
LP-1	PLANTING PLAN
LP-2	PLANTING PLAN
LD-1	LANDSCAPE DETAILS

LEGEND


PROPERTY LINE	----
EXISTING CENTERLINE	----
PROPOSED CENTERLINE	----
EXISTING EDGE OF ASPHALT	----
PROPOSED EDGE OF ASPHALT	----
EXISTING EDGE OF SHOULDER	----
PROPOSED EDGE OF SHOULDER	----
EXISTING DITCH/DIRECTION OF FLOW	----->
PROPOSED DITCH/DIRECTION OF FLOW	----->
EXISTING SANITARY SEWER/SIZE/DIRECTION OF FLOW	-----200# SAN----->
PROPOSED SANITARY SEWER/SIZE/DIRECTION OF FLOW	-----200# SAN----->
EXISTING SANITARY SERVICE	-----
PROPOSED SANITARY SERVICE	-----
EXISTING SANITARY FORCEMAIN/SIZE/DIRECTION OF FLOW	-----200# SAN F/M----->
EXISTING WATERMAIN/SIZE	-----150# W/M-----
PROPOSED WATERMAIN/SIZE	-----150# W/M-----
EXISTING WATER SERVICE	-----
PROPOSED WATER SERVICE	-----
EXISTING STORM SEWER/SIZE/DIRECTION OF FLOW	-----375# STM----->
PROPOSED STORM SEWER/SIZE/DIRECTION OF FLOW	-----375# STM----->
PROPOSED STORM SERVICE	-----
EXISTING CULVERT	=====
PROPOSED CULVERT	=====
PROPOSED SWALE LOCATION	----->
PROPOSED JOINT HYDRO, BELL AND ROGERS	-----
EXISTING GAS MAIN	-----
PROPOSED GAS MAIN	-----
EXISTING FENCELINE	-----*
PROPOSED FENCELINE	-----*
EXISTING BUSHLINE	-----
EXISTING CONTOUR	-----179.00-----
EXISTING SPOT ELEVATION	x 179.00
PROPOSED SPOT ELEVATION	x 179.00
EXISTING GRADING DIRECTION	----->
PROPOSED GRADING DIRECTION	----->
EXISTING TEMPORARY BENCHMARK	TBM
EXISTING STANDARD IRON BAR	SIB
EXISTING BOREHOLE/NUMBER	BHP
EXISTING GAS VALVE	GAS
EXISTING HYDRO TRANSFORMER	HT
EXISTING CABLE PEDESTAL	CP
EXISTING BELL PEDESTAL	BP
EXISTING BELL MAINTENANCE HOLE	BELL MH
EXISTING BELL POLE	BP
EXISTING HYDRO POLE	HP
EXISTING HYDRO GUY WIRE	GW
PROPOSED LIGHT STANDARD	LS
EXISTING TRAFFIC SIGN	TS
PROPOSED TRAFFIC SIGN	TS
PROPOSED STOP SIGN	STOP SIGN
PROPOSED STREET NAME SIGN	STREET NAME SIGN
PROPOSED SIGN (MISCELLANEOUS)	SIGN
EXISTING DECIDUOUS TREE	DT
EXISTING CONIFEROUS TREE	CT
EXISTING SANITARY MAINTENANCE HOLE/NUMBER	SAN MH17
PROPOSED SANITARY MAINTENANCE HOLE/NUMBER	SAN MH17
PROPOSED SANITARY CLEAN OUT	CO
EXISTING HYDRANT AND VALVE	HYD & WV
PROPOSED HYDRANT AND VALVE	HYD & WV
EXISTING WATER VALVE	WV
PROPOSED WATER VALVE	WV
PROPOSED CURB STOP VALVE	CSV
EXISTING BLOW-OFF	BLOWOFF
PROPOSED BLOW-OFF	BLOWOFF
EXISTING WATERMAIN PLUG AND THRUST BLOCK	WTB
PROPOSED WATERMAIN PLUG AND THRUST BLOCK	WTB
EXISTING STORM MAINTENANCE HOLE/NUMBER	STM MH20
PROPOSED STORM MAINTENANCE HOLE/NUMBER	STM MH9
EXISTING CATCH BASIN/NUMBER	CBMH 18
PROPOSED CATCH BASIN/NUMBER	CB1
PROPOSED CATCH BASIN MAINTENANCE HOLE/NUMBER	CBMH12
PROPOSED DOUBLE CATCH BASIN MAINTENANCE HOLE/NUMBER	DCBMH4
PROPOSED DOUBLE CATCH BASIN/NUMBER	DCB1
PROPOSED DITCH INLET/NUMBER	DICB2
TACTILE SURFACE INDICATORS	TSI




PHASE 2 BLOCK - 152
Contract No. : 117227



LEGEND

CATCHMENT ID 

AREA IN HECTARES 

RUNOFF COEFFICIENT

POST-DEVELOPMENT CATCHMENT AREA 

EXISTING CATCHMENT AREA (PHASE 2) 


PROPOSED OVERLAND FLOW DIRECTION 

The Consultant shall provide a Communications Plan to notify the Town and Area Residents of significant Construction activities to the satisfaction of the Town.



At a minimum the Plan should provide:

- Installation of a Project Notification Sign, 1.2 m x 2.4 m minimum, to Town template, at each construction access to the Lands and visually obvious to the public, at least two (2) weeks before the construction start date, and maintained for full duration of construction.
- Notification of the construction project to property owners as deemed appropriate in consultation with Development Engineering via hand/mail delivery.
- Schedules of intended site activities updated routinely, (typically, weekly to bi-weekly).
- A minimum of two (2) weeks' notice following Town approval and prior to commencement of:
 - o Significant site activities such as site alteration works e.g. tree clearing & grubbing, commencement of site servicing/grading, placement of asphalt, concrete curbs and sidewalk, and landscaping.
 - o Off-site works on Town Owned Lands/Roads following receipt of a Municipal Land Use Permit (MLUP).


DISCLAIMER AND COPYRIGHT CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED. TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.	BENCHMARKS TBM1 - ELEVATION 226.036 TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21) TBM2 - ELEVATION 224.127 RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD	NOTES Town of Blue Mountains Planning and Development Services Accepted For Construction AFC Drawings are only valid as part and upon execution of a Development Agreement <i>Signature</i> 30-Jun-2020 signature date	<table><tr><th>No.</th><th>REVISION DESCRIPTION</th><th>DATE</th></tr><tr><td>1.</td><td>1ST SUBMISSION</td><td>JUL 4/19</td></tr><tr><td>2.</td><td>2ND SUBMISSION</td><td>NOV 20/19</td></tr><tr><td>3.</td><td>3RD SUBMISSION</td><td>MAR 20/20</td></tr><tr><td>4.</td><td>4TH SUBMISSION</td><td>APR 27/20</td></tr></table>	No.	REVISION DESCRIPTION	DATE	1.	1ST SUBMISSION	JUL 4/19	2.	2ND SUBMISSION	NOV 20/19	3.	3RD SUBMISSION	MAR 20/20	4.	4TH SUBMISSION	APR 27/20	ENGINEER STAMP 	MANORWOOD HOMES - SECOND NATURE PHASE 2 BLOCK - 152 TOWN OF THE BLUE MOUNTAINS	STORM DRAINAGE PLAN	<table><tr><td>DESIGN: DEP/AO</td><td>FILE: 117227</td><td>DWG:</td></tr><tr><td>DRAWN: DEP</td><td>DATE: SEP 2017</td><td>SD-1</td></tr><tr><td>CHECK: DJH</td><td>SCALE: 1:500</td><td></td></tr></table>	DESIGN: DEP/AO	FILE: 117227	DWG:	DRAWN: DEP	DATE: SEP 2017	SD-1	CHECK: DJH	SCALE: 1:500	
No.	REVISION DESCRIPTION	DATE																													
1.	1ST SUBMISSION	JUL 4/19																													
2.	2ND SUBMISSION	NOV 20/19																													
3.	3RD SUBMISSION	MAR 20/20																													
4.	4TH SUBMISSION	APR 27/20																													
DESIGN: DEP/AO	FILE: 117227	DWG:																													
DRAWN: DEP	DATE: SEP 2017	SD-1																													
CHECK: DJH	SCALE: 1:500																														

STORM SEWER DESIGN SHEET - 5 YEAR (DESIGN)										Approved:									
										Project Name: Second Nature - Block 152 Project Number: 117227 Municipality: Town of The Blue Mountains Designed By: LC Date: December 19, 2018 Revised By: AO Date: February 14, 2020 Checked By: JPA Date: February 14, 2020 Revision Number: 6									
IDF Curve Coefficients																			
Storm																			
2 Year																			
5 Year																			
25 Year																			
100 Year																			
Manning's Coefficient																			
CSP																			
Conc.																			
PVC																			

STREET NAME	AREA LABEL	UPSTREAM MAINTENANCE HOLE	DOWNSTREAM MAINTENANCE HOLE	TRIBUTARY AREA - A	RUNOFF COEFFICIENT - C	INDIVIDUAL A x C	CUMULATIVE AREA	CUMULATIVE A x C	TIME OF CONCENTRATION	RAINFALL INTENSITY	PEAK FLOW	MANNING'S ROUGHNESS COEFFICIENT	LENGTH	SLOPE	ACTUAL DIAMETER	FULL FLOW VELOCITY	FULL FLOW CAPACITY	ACTUAL VELOCITY	TIME OF FLOW	CALCULATED PIPE DIAMETER	PERCENT PIPE FULL	TIME OF CONCENTRATION
		MH No.	MH No.	ha			ha		min.	mm/hr	cms		m	m/m	mm	m/s	cms	m/s	min	mm	%	min
Phase 2																						
Crosswinds Boulevard	201 + EXT2	HDW1	STM MH104	0.15	0.50	0.08	0.15	0.08	15.00	79.39	0.017	0.013	11.0	5.6%	300	3.24	0.229	1.81	0.10	112	7.2%	15.10
Crosswinds Boulevard	202 + EXT1	HDW2	STM MH104	0.16	0.50	0.08	0.16	0.08	15.00	79.39	0.018	0.013	16.0	3.9%	300	2.70	0.191	1.61	0.17	123	9.2%	15.17
Block 152	203 + EXT3	HDW3	STM MH104	0.49	0.65	0.32	0.49	0.32	15.00	79.39	0.070	0.013	30.5	2.7%	300	2.25	0.159	2.04	0.25	221	44.2%	15.25
Crosswinds Boulevard		STM MH104	CBMH103	-	-	-	0.80	0.47	15.25	78.45	0.103	0.013	40.0	0.6%	375	1.23	0.136	1.23	0.54	338	76.0%	15.79
Crosswinds Boulevard	204	CBMH103	CBMH102	0.18	0.50	0.09	0.98	0.56	15.79	76.49	0.120	0.013	48.5	0.6%	375	1.23	0.136	1.23	0.68	358	88.3%	16.45
Street B	105	CBMH6	CBMH7	0.05	0.65	0.03	0.05	0.03	15.00	79.39	0.007	0.013	60.2	2.3%	300	2.07	0.147	1.04	0.96	97	4.9%	15.96
Street B	106 + EXT5	RLCB 7	CBMH7	0.47	0.65	0.31	0.47	0.31	15.00	79.39	0.067	0.013	33.5	0.8%	300	1.22	0.086	1.22	0.46	273	77.9%	15.46
Street B	107	CBMH7	CBMH8	0.22	0.65	0.14	0.74	0.48	15.96	75.89	0.101	0.013	41.6	0.5%	375	1.12	0.124	1.12	0.62	348	81.8%	16.58
Street B	108	CBMH8	CBMH9	0.21	0.65	0.14	0.95	0.62	16.58	73.83	0.127	0.013	21.7	1.2%	450	1.96	0.312	1.74	0.21	321	40.5%	16.79
109 + EXT4	RLCB9	CBMH9	CBMH10	0.34	0.65	0.22	0.34	0.22	15.00	79.39	0.049	0.013	33.3	1.0%	300	1.37	0.097	1.28	0.43	232	50.4%	15.43
Street B	110	CBMH9	CBMH10	0.14	0.65	0.09	1.43	0.93	16.79	73.17	0.189	0.013	54.0	0.5%	525	1.40	0.304	1.39	0.65	439	62.1%	17.44
Street B	111	CBMH11	CBMH12	0.06	0.65	0.04	0.06	0.04	15.00	79.39	0.009	0.013	12.4	0.5%	300	0.97	0.068	0.62	0.33	138	12.6%	15.33
Street B	112	CBMH12	CBMH10	0.05	0.65	0.03	0.11	0.07	15.33	78.14	0.016	0.013	23.1	0.5%	300	0.97	0.068	0.73	0.53	172	22.7%	15.86
Street B	113	CBMH10	CBMH13	0.10	0.65	0.07	1.64	1.07	17.44	71.19	0.211	0.013	6.0	0.3%	525	1.09	0.236	1.09	0.09	503	89.5%	17.53
Street B	114	CBMH13	CBMH14	0.10	0.65	0.07	1.74	1.13	17.53	70.92	0.223	0.013	13.1	2.4%	525	3.08	0.666	2.60	0.08	348	33.4%	17.61
Street B	115	CBMH14	CBMH102A	0.17	0.65	0.11	1.91	1.24	17.61	70.68	0.244	0.013	16.5	0.7%	525	3.66	0.960	1.66	0.17	453	67.7%	17.78
Crosswinds Boulevard	206	CBMH102A	CBMH102	0.15	0.50	0.08	2.06	1.32	17.78	70.20	0.257	0.013	9.5	1.4%	525	2.53	0.503	2.19	0.07	408	51.0%	17.85
Crosswinds Boulevard	207	CBMH102	STM MH101	0.07	0.50	0.03	3.11	1.91	16.45	74.27	0.395	0.013	31.7	1.0%	600	2.17	0.614	2.17	0.24	508	64.3%	16.69
Street C	101	DCBMH1	CBMH2	0.12	0.65	0.08	0.12	0.08	15.00	79.39	0.017	0.013	28.3	1.7%	300	1.78	0.126	1.18	0.40	142	13.5%	15.40
Street A	102	CBMH2	CBMH3	0.06	0.65	0.04	0.18	0.12	15.40	77.89	0.025	0.013	55.4	2.3%	300	2.07	0.147	1.46	0.63	155	17.3%	16.03
Street A	103	CBMH3	CBMH4	0.16	0.65	0.10	0.34	0.22	16.03	75.66	0.046	0.013	29.3	0.7%	300	1.14	0.081	1.11	0.44	244	57.4%	16.47
Street A	104	CBMH4	STM MH5	0.11	0.65	0.07	0.45	0.29	16.47	74.19	0.060	0.013	22.3	0.7%	300	1.14	0.081	1.14	0.52	269	74.5%	16.80
Street A	STM MH5	STM MH106	STM MH106	-	-	-	0.45	0.29	16.80	73.15	0.059	0.013	22.7	1.2%	375	1.74	0.192	1.43	0.26	241	30.9%	17.06
Crosswinds Boulevard	209	STM MH106	CBMH105	-	-	-	0.45	0.29	17.06	72.33	0.059	0.013	22.4	1.0%	375	1.59	0.175	1.33	0.28	249	33.5%	17.34
Crosswinds Boulevard	209	CBMH105	STM MH101	0.24	0.50	0.12	0.69	0.41	17.34	71.48	0.082	0.013	22.3	1.0%	450	1.79	0.285	1.44	0.26	281	28.6%	17.60
Phase 3																						
Street 'C'	-	STM MH101	CBMH100	-	-	-	3.80	2.33	16.69	73.48	0.475	0.013	24.0	1.0%	675	2.35	0.841	2.28	0.18	548	56.5%	16.87
Street 'C'	301	CBMH100	CBMH200	0.10	0.50	0.05	3.90	2.38	16.87	72.93	0.481	0.013	41.5	1.8%	675	3.15	1.128	2.84	0.24	490	42.7%	17.11
Street 'C'	302	CBMH200	STM MH201	0.25	0.50	0.12	4.15	2.50	17.11	72.18	0.501	0.013	11.4	0.7%	675	1.97	0.703	1.97	0.10	594	71.3%	17.21
Street 'C'	-	STM MH201	CBMH202	-	-	-	4.15	2.50	17.21	71.89	0.499	0.013	36.7	1.1%	675	2.45	0.882	2.39	0.25	545	56.6%	17.46
Street 'C'	303	CBMH202	CBMH203	0.03	0.50	0.01	4.17	2.51	17.46	71.12	0.496	0.013	25.0	2.0%	675	3.32	1.189	2.98	0.14	486	41.8%	17.60
Street 'C'	304	CBMH203	STM MH204	0.29	0.50	0.15	4.46	2.66	17.60	70.71	0.522	0.013	47.9	2.6%	675	3.79	1.355	3.33	0.24	472	38.5%	17.84
Street 'G'	-	STM MH205	DCBMH206	-	-	-	-	-	15.00	79.39	0.006	0.013	82.3	0.5%	300	0.97	0.068	0.56	2.43	120	8.9%	17.43
Street 'G'	305	DCBMH206	STM MH204	0.91	0.50	0.45	0.91	0.45	17.43	71.21	0.090	0.013	16.9	0.5%	375	1.12	0.124	1.12	0.28	332	72.5%	17.71
Street 'C'	306	STM MH204	CBMH207	0.11	0.50	0.05	5.48	3.17	17.84	70.02	0.616	0.013	55.3	0.8%	675	2.10	0.752	2.10	0.44	626	81.9%	18.28
Street 'C'	307	CBMH207	STM MH208	0.22	0.50	0.11	5.70	3.28	18.28	68.80	0.626	0.013	45.1	0.8%	675	2.10	0.752	2.10	0.36	630	83.2%	18.64
Street 'E'	-	CBMH209	CBMH210	-	-	-	-	-	15.00	79.39	0.006	0.013	62.9	0.6%	300	1.06	0.075	0.60	1.74	116	8.0%	16.74
Street 'E'	308	CBMH210	DCBMH211	0.47	0.50	0.24	0.47	0.24	16.74	73.33	0.048	0.013	69.3	0.5%	300	0.97	0.068	0.97	1.19	263	70.6%	17.93
Street 'E'	309	DCBMH211	STM MH208	0.84	0.50	0.42	1.31	0.66	17.93	69.77	0.127	0.013	20.0	0.5%	450	1.27	0.202	1.26	0.26	379	63.1%	18.20
Street 'C'	310	STM MH208	CBMH212	0.10	0.50	0.05	7.11	3.98	18.64	67.84	0.750	0.013	45.6	0.8%	750	2.25	0.996	2.25	0.54	674	75.4%	18.98
Street 'C'	311	CBMH212	STM MH213	0.16	0.50	0.08	7.27	4.06	18.98	66.96	0.756	0.013	55.2	0.8%	750	2.25	0.996	2.25	0.41	676	75.9%	19.38
Street 'D'	-	DCBMH214	DCBMH215	-	-	-	-	-	15.00	79.39	0.006	0.013	86.9	0.5%	300	0.97	0.068	0.56	2.57	120	8.8%	17.57
Street 'D'	312	DCBMH215	STM MH213	0.67	0.50	0.33	0.67	0.33	17.57	70.81	0.066	0.013	15.6	0.5%	300	0.97	0.068	0.97	0.27	295	96.1%	17.84
Street 'C'	313	STM MH213	CBMH216	0.08	0.50	0.04	8.02	4.44	19.38	65.94	0.813	0.013	32.7	0.6%	825	2.08	1.112	2.08	0.26	733	73.1%	18.63
Street 'C'	314	CBMH216	CBMH217	0.09	0.50	0.05	8.11	4.48	19.65	65.30	0.813	0.013	32.8	0.6%	825	2.08	1.112	2.08	0.26	733	73.1%	18.91



DISCLAIMER AND COPYRIGHT CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED. TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.	BENCHMARKS TBM1 - ELEVATION 226.036 TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21) TBM2 - ELEVATION 224.127 RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD	NOTES Town of Blue Mountains Planning and Development Services Accepted For Construction AFC Drawings are only valid as part and upon execution of a Development Agreement <i>[Signature]</i> 30 June 2020 signature date	<table><tr><th>No.</th><th>REVISION DESCRIPTION</th><th>DATE</th></tr><tr><td>1.</td><td>2ND SUBMISSION</td><td>NOV 20/19</td></tr><tr><td>2.</td><td>3RD SUBMISSION</td><td>MAR 20/20</td></tr><tr><td>3.</td><td>4TH SUBMISSION</td><td>APR 27/20</td></tr></table>	No.	REVISION DESCRIPTION	DATE	1.	2ND SUBMISSION	NOV 20/19	2.	3RD SUBMISSION	MAR 20/20	3.	4TH SUBMISSION	APR 27/20	ENGINEER STAMP LICENCED PROFESSIONAL ENGINEER <i>[Signature]</i> D. J. HURLEY Apr 27/20 PROVINCE OF ONTARIO	MANORWOOD HOMES - SECOND NATURE PHASE 2 BLOCK - 152 TOWN OF THE BLUE MOUNTAINS	TATHAM ENGINEERING		
No.	REVISION DESCRIPTION	DATE																		
1.	2ND SUBMISSION	NOV 20/19																		
2.	3RD SUBMISSION	MAR 20/20																		
3.	4TH SUBMISSION	APR 27/20																		
WATER DISTRIBUTION PLAN						DESIGN: VP/AO	FILE: 117227	DWG:												
						DRAWN: VP	DATE: SEP 2017	WD-1												
						CHECK: DJH	SCALE: 1:500													



KEY PLAN

SILTATION & EROSION CONTROL NOTES

1. ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. SEDIMENT AND EROSION CONTROL MEASURES THAT ARE DESIGNED TO CONTROL RUNOFF FROM SPECIFIC AREAS MUST BE INSTALLED PRIOR TO ANY DISTURBANCE OF THAT PART OF THE SITE. THE LOCATION OF ALL SILTATION AND EROSION CONTROL WORKS TO BE REVIEWED ON SITE AND MAY BE REVISED AS DIRECTED BY THE ENGINEER.
2. THE CONTRACTOR MAY CONSIDER ALTERNATIVE SEDIMENT AND EROSION CONTROL MEASURES. SUCH MEASURES MUST BE PRESENTED IN WRITING TO THE ENGINEER FOR APPROVAL BY THE TOWN OF THE BLUE MOUNTAINS AND THE GREY SAUBLE CONSERVATION AUTHORITY.
3. THE CONTRACTOR SHALL HAVE MATERIALS AVAILABLE ON-SITE TO REPAIR SEDIMENT AND EROSION CONTROL MEASURES IN THE EVENT OF UNFORESEEN CONDITIONS: HIGH WATER, EXTREME RAINFALL EVENTS, ETC.
4. ALL EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSPECTED, CLEANED AND MAINTAINED BY THE CONTRACTOR AFTER EACH STORM EVENT. ALL WORKS WILL BE INSPECTED BY THE ENGINEER BI-WEEKLY AND AFTER EACH MAJOR STORM EVENT.
5. CONSTRUCTION OF ALL SILTATION AND EROSION CONTROL WORKS ARE TO BE IN ACCORDANCE WITH THE FOLLOWING STEPS:
 - 5.1. INSTALL STONE MUD MAT AS PER TOWN STANDARD.
 - 5.2. INSTALL SILT FENCE AS PER OPSD 219.130.
 - 5.3. INSTALL ROCK FLOW CHECKS AS PER OPSD 219.210.
 - 5.4. INSTALL TEMPORARY CATCH BASIN SEDIMENT TRAPS ON ALL NEW AND EXISTING CATCH BASIN STRUCTURES. SEDIMENT TRAPS TO BE RECTANGULAR CBST BY LAYFIELD OR APPROVED EQUAL. ALL CATCH BASIN SEDIMENT TRAPS TO REMAIN IN PLACE AND MAINTAINED REGULARLY UNTIL BASE COURSE ASPHALT IS PLACED AND LOT GRADING IS COMPLETE.
6. ALL CONSTRUCTION VEHICLES TO ACCESS SITE USING THE DESIGNATED CONSTRUCTION ACCESS.
7. EROSION AND SEDIMENT CONTROL MEASURES TO BE REMOVED BY THE CONTRACTOR ONCE GROUND COVER IS ESTABLISHED AND LANDSCAPING IS COMPLETE AND AS APPROVED BY THE ENGINEER.
8. STOCKPILE LOCATIONS ARE TO BE APPROVED BY THE ENGINEER.
9. PROVIDE FENCE OR APPROVED EQUAL ACROSS ALL CONSTRUCTION ACCESSES DURING PERIODS OF INACTIVITY.
10. CONSTRUCTION AREAS THAT EXCEED 30 DAYS OF INACTIVITY SHALL BE STABILIZED BY SEEDING AND/OR AS DIRECTED BY THE TOWN. THIS IS TO INCLUDE STOCKPILES OF FILL AND TOPSOIL.

STONE MUD MAT NOTES:

1. LENGTH AS REQUIRED BUT NOT LESS THAN 35m.
2. WIDTH OF 7m BUT NOT LESS THAN THE WIDTH AT POINTS WHERE INGRESS AND EGRESS OCCURS.
3. TERRAFIX 270R GEOTEXTILE (OR APPROVED EQUIVALENT) TO BE PLACED OVER THE ENTIRE AREA OF MAT PRIOR TO PLACING STONE.
4. ACCESSES SHALL BE PROVIDED WITH A CULVERT IF REQUIRED FOR ROADSIDE SURFACE DRAINAGE.
5. THE CONTRACTOR SHALL BE RESPONSIBLE TO MAINTAIN THE ACCESS AND PROVIDE ADDITIONAL STONE TO THE SATISFACTION OF THE TOWN SUCH THAT SEDIMENT IS NOT TRACKED ONTO THE ADJACENT ROADWAY.
6. THE TOWN'S ENGINEER MAY DIRECT ADDITIONAL MEASURES TO BE TAKEN TO ELIMINATE MUD TRACKING UP TO AND INCLUDING VEHICLE WASHING PRIOR TO EXITING THE SITE.
7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEARING ANY SEDIMENT THAT IS TRACKED ONTO MUNICIPAL RIGHTS-OF-WAY TO THE SATISFACTION OF THE TOWN.
8. STONE MUD MAT SHALL BE INSPECTED DAILY AND REINSTATED ACCORDINGLY.

LEGEND

- PROPOSED SILT FENCE
- EXISTING SILT FENCE
- ROCK FLOW CHECK DAM
- PROPOSED INTERCEPTOR SWALE
- EXISTING INTERCEPTOR SWALE

DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS

TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES

Town of Blue Mountains
Planning and Development Services
Accepted For Construction
AFC Drawings are only valid as part and upon execution of a Development Agreement
signature date 30 June 2020

No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP
1.	2ND SUBMISSION	NOV 20/19	
2.	3RD SUBMISSION	MAR 20/20	
3.	4TH SUBMISSION	APR 27/20	




MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS

EROSION AND SEDIMENT CONTROL PLAN



DESIGN: VP	FILE: 117227	DWG: ES-1
DRAWN: VP	DATE: SEP 2017	
CHECK: DJH	SCALE: 1:500	



DISCLAIMER AND COPYRIGHT
CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.
TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS
TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)
TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES
Town of Blue Mountains
Planning and Development Services
Accepted For Construction
AFC Drawings are only valid as part and upon execution of a Development Agreement
Signature: [Signature] Date: 30-Jun-2020

No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	JUL 4/19
2.	2ND SUBMISSION	NOV 20/19
3.	3RD SUBMISSION	MAR 18/20
4.	4TH SUBMISSION	APR 27/20

ENGINEER STAMP


D. J. HURLEY
PROFESSIONAL ENGINEER
PROVINCE OF ONTARIO

**MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS**

SITE SERVICING PLAN

TATHAM ENGINEERING

DESIGN: MR/AO	FILE: 117227	DWG: SS-1
DRAWN: MR	DATE: SEP 2017	
CHECK: DJH	SCALE: 1:500	



DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS

TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES

BUILDING ELEVATIONS TO BE COMPLETED BY HUNT DESIGN ARCHITECTS INC.

ALL FUTURE FENCING MUST BE INSTALLED WHOLLY ON PRIVATE LAND.

No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP
1.	1ST SUBMISSION	JUL 4/19	
2.	2ND SUBMISSION	NOV 20/19	
3.	3RD SUBMISSION	MAR 20/20	
4.	4TH SUBMISSION	APR 27/20	

**MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS**



SITE GRADING PLAN

**TATHAM
ENGINEERING**







DESIGN: MR/AO
FILE: 117227
DWC:

DRAWN: MR
DATE: SEP 2017
SG-1

CHECK: DJH
SCALE: 1:250



KEY PLAN



Town of Blue Mountains
Planning and Development Services
Accepted For Construction
AFC Drawings are only valid as part and upon execution of a
Development Agreement
Russell Wood 30-Jun-2020
signature date

HUNT
DESIGN ASSOCIATES INC.
www.huntdesign.ca
8966 Woodbine Avenue, Suite 200, Markham, ON L3R 0J7
T 905.737.5133 // F 905.737.7326
REGISTRATION INFORMATION
HUNT DESIGN ASSOCIATES INC.

DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS

TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES

BUILDING ELEVATIONS TO BE COMPLETED BY HUNT DESIGN ARCHITECTS INC.
ALL FUTURE FENCING MUST BE INSTALLED WHOLLY ON PRIVATE LAND.

No.	REVISION DESCRIPTION	DATE
1.	3RD SUBMISSION	MAR 20/20
2.	4TH SUBMISSION	APR 27/20

ENGINEER STAMP





**MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS**






**SITE GRADING
AND DETAILS PLAN**

**TATHAM
ENGINEERING**

DESIGN: MR/AO	FILE: 117227	DWG: SG-3
DRAWN: SBU	DATE: SEP 2017	
CHECK: DJH	SCALE: 1:250	



DISCLAIMER AND COPYRIGHT CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED. TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.		BENCHMARKS TBM1 - ELEVATION 226.036 TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21) TBM2 - ELEVATION 224.127 RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD		NOTES		<table border="1"><thead><tr><th>No.</th><th>REVISION DESCRIPTION</th><th>DATE</th></tr></thead><tbody><tr><td>1.</td><td>2ND SUBMISSION</td><td>NOV 20/19</td></tr><tr><td>2.</td><td>3RD SUBMISSION</td><td>MAR 20/20</td></tr><tr><td>3.</td><td>4TH SUBMISSION</td><td>APR 27/20</td></tr></tbody></table>		No.	REVISION DESCRIPTION	DATE	1.	2ND SUBMISSION	NOV 20/19	2.	3RD SUBMISSION	MAR 20/20	3.	4TH SUBMISSION	APR 27/20	ENGINEER STAMP 		MANORWOOD HOMES - SECOND NATURE PHASE 2 BLOCK - 152 TOWN OF THE BLUE MOUNTAINS		TATHAM ENGINEERING	
No.	REVISION DESCRIPTION	DATE																							
1.	2ND SUBMISSION	NOV 20/19																							
2.	3RD SUBMISSION	MAR 20/20																							
3.	4TH SUBMISSION	APR 27/20																							
PLAN AND PROFILE STREET A STA. 0+995 TO STA. 1+130						DESIGN: VP DRAWN: VP CHECK: DJH		FILE: 117227 DATE: SEP 2017 SCALE: 1:250/1:25		PP-1															



DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.


TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS

TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES



No.	REVISION DESCRIPTION	DATE
1.	2ND SUBMISSION	NOV 20/19
2.	3RD SUBMISSION	MAR 20/20
3.	4TH SUBMISSION	APR 27/20

ENGINEER STAMP







MANORWOOD HOMES - SECOND NATURE PHASE 2 BLOCK - 152 TOWN OF THE BLUE MOUNTAINS

PLAN AND PROFILE
STREET A STA. 1+130 TO STA. 1+174
SERVICE CORRIDOR STA. 3+992 TO STA. 4+051



DESIGN: VP	FILE: 117227	DWG: PP-2
DRAWN: VP	DATE: SEP 2017	
CHECK: DJH	SCALE: 1:250/1:25	



CHANGING	EXISTING C/L ELEV	PROPOSED C/L ELEV
2+140	223.85	223.85
2+160	223.65	223.65
2+180	223.45	223.45
2+200	223.25	223.25
2+220	222.79	222.79
2+240	221.95	221.95

CHANGING	EXISTING C/L ELEV	PROPOSED C/L ELEV
5+000	223.37	223.37
5+020	222.27	222.27
5+040	222.19	222.19

DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS

TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES

Town of Blue Mountains
Planning and Development Services
Accepted For Construction

AFC Drawings are only valid as part and upon execution of a Development Agreement

Signature 30 June 2020

No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP
1.	2ND SUBMISSION	NOV 20/19	
2.	3RD SUBMISSION	MAR 20/20	
3.	4TH SUBMISSION	APR 27/20	


MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS

PLAN AND PROFILE
STREET B STA. 2+140 TO STA. 2+258
SERVICE CORRIDOR STA. 4+995 TO STA. 5+054



DESIGN: VP
DRAWN: VP
CHECK: DJH

FILE: 117227
DATE: SEP 2017
SCALE: 1:250

DWG: **PP-4**



KEY PLAN



DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS

TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES

Town of Blue Mountains
Planning and Development Services
Accepted For Construction
AFC Drawings are only valid as part and upon execution of a Development Agreement
Signature 30 June 2020
Date

No.

REVISION DESCRIPTION	DATE
1. 2ND SUBMISSION	NOV 20/19
2. 3RD SUBMISSION	MAR 18/20
3. 4TH SUBMISSION	APR 27/20

ENGINEER STAMP




MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS

PLAN AND PROFILE
STREET C
STA. 2+968 TO STA. 3+029



DESIGN: VP	FILE: 117227	DWG: PP-5
DRAWN: VP	DATE: SEP 2017	
CHECK: DJH	SCALE: 1:250	



1	SOLID YELLOW,10cm
2	SOLID DOUBLE YELLOW,10cm
3	363 BROKEN YELLOW,10cm
4	SOLID YELLOW,20cm
5	SOLID WHITE,10cm
6	333 BROKEN WHITE,10cm
7	363 BROKEN WHITE,10cm
8	393 BROKEN WHITE,10cm
9	SOLID WHITE,20cm
10	111 BROKEN WHITE,20cm
11	333 BROKEN WHITE,20cm
12	333 BROKEN WHITE,30cm
13	SOLID WHITE,30cm
14	SOLID WHITE,45cm
15	SOLID WHITE,60cm
16	1-0.6-1 WHITE,45cm
17	1.8-1.8-1.8 WHITE,20cm
20	SYMBOLS
] [LIMITS OF MARKINGS	

- NOTES:
1. 333, 363, 393, Denotes Pavement Marking Spacing (ie., 3 m line, 3 m gap, 3 m line)
 2. ① Denotes PAVEMENT MARKING, PAINT
 3. [1] Denotes PAVEMENT MARKING, TEMPORARY
 4. △ Denotes PAVEMENT MARKING, TEMPORARY-REMOVABLE
 5. ① Denotes PAVEMENT MARKING, DURABLE



DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS

TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES

Town of Blue Mountains
Planning and Development Services
Accepted For Construction

AFC Drawings are only valid as part and upon execution of a Development Agreement

Signature 30-Jun-2020
signature date



No.	REVISION DESCRIPTION	DATE	ENGINEER STAMP
1.	3RD SUBMISSION	MAR 20/20	
2.	4TH SUBMISSION	APR 27/20	

**MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS**

**PAVEMENT MARKING
AND SIGNAGE PLAN**

TATHAM ENGINEERING

DESIGN: SBU	FILE: 117227	DWG:
DRAWN: SBU	DATE: SEP 2017	PM-1
CHECK: DJH	SCALE: 1:500	



KEY PLAN

LEGEND


- PROP. STOP SIGN
- PROP. STREET SIGN
- PROP. LIGHT STANDARD
- PROP. WALKWAY LIGHT BOLLARD
- PROPOSED HYDRO TRANSFORMER & GROUND GRID
- PROPOSED ROAD CROSSING INCL. H-HYDRO, C-CABLE, B-BELL, G-GAS (GAS NO DUCT) NOTE: CONCRETE TO BE ENCASED TO 0.30m PAST BACK OF CURB.
- HCBG
- UT
- PROP. UTILITY TRENCH
- PROP. HYDRO SERVICE
- PROP. BELL PEDESTAL (PHASE 1 ONLY)
- PROP. BELL - FLUSH TO GRADE LEVEL BOX IN BLVD. (LARGE)
- PROP. BELL - FLUSH TO GRADE LEVEL BOX AT LOT (SMALL)
- PROP. CABLE PEDESTAL
- PROP. GAS VALVE
- PROP. CANADA POST MAILBOX MODEL E201 WITH E101 CONC. BASE.
- BLOCK 2/6 UNITS
- BLOCK/UNITS NUMBER
- 2-4
- PROP. SANITARY SERVICE
- PROP. STORM SERVICE
- PROP. WATER SERVICE

NOTES

THIS PLAN TO BE USED FOR REFERENCE PURPOSES ONLY. SEE PLANS BY UTILITY PROVIDERS FOR CONSTRUCTION DETAILS.

REFER TO TYPICAL ROAD CROSS SECTION ON DWG. DE-1 FOR LOCATION OF UTILITIES.

DISCLAIMER AND COPYRIGHT CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED. TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.		BENCHMARKS TBM1 – ELEVATION 226.036 TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99–21) TBM2 – ELEVATION 224.127 RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD		NOTES Town of Blue Mountains Planning and Development Services Accepted For Construction AFC Drawings are only valid as part and upon execution of a Development Agreement  signature 30-Jun-2020 date		<table><tr><th>No.</th><th>REVISION DESCRIPTION</th><th>DATE</th></tr><tr><td>1.</td><td>4TH SUBMISSION</td><td>APR 27/20</td></tr></table>		No.	REVISION DESCRIPTION	DATE	1.	4TH SUBMISSION	APR 27/20	ENGINEER STAMP 		MANORWOOD HOMES - SECOND NATURE PHASE 2 BLOCK - 152 TOWN OF THE BLUE MOUNTAINS				
No.	REVISION DESCRIPTION	DATE																		
1.	4TH SUBMISSION	APR 27/20																		
COMPOSITE UTILITY PLAN								DESIGN: AO		FILE: 117227		DWG:								
								DRAWN: SBU		DATE: SEP 2017		CUP-1								
								CHECK: DJH		SCALE: 1:500										




		HORIZONTAL BEND		VERTICAL BEND		DEAD END (NO BEND ANGLE)
PIPE DIA.	BEND ANGLE	RESTRAINT LENGTH (m)	RESTRAINT 1 LENGTH (m)	RESTRAINT 2 LENGTH (m)	RESTRAINT LENGTH (m)	
150ø	90°	3.7	—	—	11.6	
	45°	1.6	4.9	1.5		
	22.5°	0.9	2.5	0.9		
	11°	0.6	1.3	0.6		
200ø	90°	4.6	—	—	15.0	
	45°	2.2	6.1	2.2		
	22.5°	0.9	3.1	1.0		
	11°	0.6	1.6	0.6		
300ø	90°	6.4	—	—	21.4	
	45°	2.8	8.9	2.8		
	22.5°	1.5	4.3	1.5		
	11°	0.9	3.4	0.9		

1. CONTRACTOR TO REPORT IN WRITING TO THE ENGINEER ANY CHANGES TO SOIL OR SITE CHARACTERISTIC THAT MAY ALTER THE PIPE RESTRAINT CALCULATION.
2. THE CONTRACTOR IS RESPONSIBLE TO CONFIRM THRUST RESTRAINT REQUIREMENTS WITH THE PIPE AND RESTRAINT MANUFACTURERS.
3. VALVES TO BE RESTRAINED AS IF THEY ARE DEAD ENDS.

MATERIAL: PVC
TYPE: ML (SILTS, VERY FINE SANDS, SILTY OR CLAYEY FINE SANDS)
RY FACTOR: 1.5 TO 1
CH TYPE: 5 (PIPE BEDDED IN COMPACT GRANULAR MATERIAL)
H OF BURY: 1.8m (6 ft)
PRESSURE: 1035 kPa (150 p.s.i.)

PIPE MATERIAL: PVC
SOIL TYPE: ML (SILTS, VERY FINE SANDS, SILTY OR CLAYEY FINE SANDS)
SAFETY FACTOR: 1.5 TO 1
TRENCH TYPE: 5 (PIPE BEDDED IN COMPACT GRANULAR MATERIAL)
DEPTH OF BURY: 1.8m (6 ft)
TEST PRESSURE: 1035 kPa (150 p.s.i.)

PROGRAM: SIGMA IRON - RESTRAINT LENGTH CALCULATOR 1.0



1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH TOWN OF THE BLUE MOUNTAINS STANDARDS AND OPS STANDARDS, WHERE CONFLICT OCCURS, TOWN STANDARDS TO GOVERN.
2. UNLESS OTHERWISE NOTED, ALL DIMENSIONS ARE IN MILLIMETERS AND ALL ELEVATIONS ARE IN METERS.
3. THE CONTRACTOR MUST OBTAIN A ROAD OCCUPANCY PERMIT FROM PUBLIC WORKS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
4. THE OWNER'S ENGINEER SHALL PROVIDE BENCHMARK ELEVATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE DETAILED LAYOUT OF THE WORK.
5. ALL PROPERTY BARS TO BE PRESERVED AND REPLACED BY OLS AT CONTRACTOR'S EXPENSE IF REMOVED/DAMAGED DURING CONSTRUCTION.
6. THE CONTRACTOR SHALL MAKE ARRANGEMENTS FOR THE SUPPLY OF TEMPORARY WATER AND POWER.
7. Dewatering to be carried out in accordance with OPSS.MUNI 517 and OPSS.MUNI 518. MAINTAIN ALL TRENCHES IN A DRY CONDITION: A MECP PERMIT TO TAKE WATER (PTW) WILL BE OBTAINED FOR THIS PROJECT.
8. ALL TOPSOIL SHALL BE STRIPPED AND STOCKPILED AT A LOCATION APPROVED BY THE ENGINEER. ALL LOTS TO BE ROUGH GRADED AND COMPACTED TO 95% STANDARD PROCTOR DENSITY PRIOR TO PLACING ANY ROADWAY GRANULAR MATERIALS.
9. ALL ENGINE VIBRATING PUMPS TO BE ADEQUATELY SILENCED, SUITABLE FOR OPERATION IN A RESIDENTIAL DISTRICT.
10. ALL INSTALLATION AND TESTING OF SEWERS, WATERMAIN AND APPURTENANCES TO BE IN ACCORDANCE WITH MUNICIPAL STANDARDS AND FURTHER SUPPORTED AS NECESSARY BY OPSS 407, OPSS 408, OPSS.MUNI 409, OPSS.MUNI 410, OPSS.MUNI 421, AND OPSS.MUNI 441 AND ALL SPECIFICATIONS REFERENCED WITHIN THESE SECTIONS.
11. MAINTENANCE HOLES ARE 1200 mm DIAMETER, UNLESS OTHERWISE SPECIFIED.
12. ALL STRUCTURES TO BE INSTALLED WITH FROST STRIPS TO OPSS 701.00.
13. PIPE SUPPORT AT ALL STRUCTURES TO OPSS 708.00.
14. ALL MAINTENANCE HOLE AND CATCH BASIN FRAME AND GRATES TO BE SET TO BASE COURSE ASPHALT ELEVATION TO WITHIN 3 mm. ALL GRATES TO BE RAISED TO FINISH GRADE PRIOR TO THE PLACEMENT OF SURFACE COURSE ASPHALT USING CONCRETE ADJUSTMENT UNITS. MAXIMUM COMBINED HEIGHT OF ADJUSTMENT UNITS SHALL BE 300 mm.
15. TRENCH BACKFILL TO BE SELECTIVE NATURAL OR IMPORTED SELECT SUBGRADE MATERIAL TO OPSS.MUNI 1010. BACKFILL TO BE PLACED TO MAXIMUM 200 mm THICK LIFTS (OR AS OTHERWISE DIRECTED BY THE GEOTECHNICAL CONSULTANT) AND COMPACTED TO A DRY DENSITY OF AT LEAST 95% OF THE MATERIAL'S STANDARD PROCTOR MAXIMUM DRY DENSITY (SPMDD).
16. PIPE EMBEDMENT TO BE COMPACTED TO A DRY DENSITY OF AT LEAST 95% OF THE MATERIAL'S SPMDD. BACKFILL AND EMBEDMENT TO OPSS 802.010 (FLEXIBLE PIPE), GRANULAR "A" EMBEDMENT OR OPSS 802.031 (RIGID PIPE) CLASS "B", GRANULAR "A" BEDDING, GRANULAR "B" COVER (MAX. AGGREGATE SIZE 25 mm), MINIMUM BEDDING WIDTH 150 mm. MINIMUM BEDDING DEPTH 150 mm. IF THE BEDDING MATERIAL IS NOT AVAILABLE TO FINISH GRADE, THE SUBGRADE IS UNCONFINED AT THE INVERT LEVEL IT MAY BE NECESSARY TO INCREASE THE BEDDING THICKNESS.
17. CLEAR STONE COMPLETELY WRAPPED IN FILTER FABRIC MAY BE SUBSTITUTED FOR EMBEDMENT MATERIAL IF APPROVED BY THE ENGINEER.
18. DISTURBED AREAS TO BE REINSTATED TO PREVIOUS CONDITION OR BETTER.
19. REINSTATEMENT OF ALL DISTURBED BOULEVARDES AND DITCHES TO INCLUDE REGRADEING, PLACEMENT OF TOPSOIL AND SOD/SEED IN ACCORDANCE WITH OPSS 802, OPSS.MUNI 803 AND OPSS.MUNI 804. SOD TO BE STAKED WHERE NECESSARY TO AVOID MOVEMENT.
20. TRAFFIC MARKERS AND SIGNS ARE TO BE INSTALLED IN ACCORDANCE WITH THE ONTARIO TRAFFIC MANUAL BOOK 7, LOCATION AND USE OF SIGNS ARE NOT GUARANTEED. THE CONTRACTOR IS RESPONSIBLE FOR THE PRESERVATION OF ALL EXISTING INFRASTRUCTURE/FACILITIES AS WELL AS NOTIFYING ALL UTILITY COMPANIES PRIOR TO COMMENCING WORK AND CO-ORDINATE CONSTRUCTION ACCORDINGLY.
21. ALL ON-SITE MATERIAL SHALL BE PROPERLY STORED, SECURED, MONITORED AND COVERED AS REQUIRED. SPECIFICALLY, ALL TOPSOIL SHALL BE COVERED AND STORED ON SITE.
22. SIGNS TO COMPLY WITH THE TOWN OF THE BLUE MOUNTAINS SIGN BY-LAW.
23. ALL FUTURE FENCING SHALL BE INSTALLED WHOLLY ON PRIVATE LAND.

1. SUBGRADE AND BOULEVARD MATERIAL TO BE COMPACTED TO A DRY DENSITY OF AT LEAST 95% OF THE MATERIAL'S SPMD. SUBGRADE TO BE PROOF ROLLED AND CERTIFIED PRIOR TO PLACING GRANULAR 'B'.
2. GRANULAR 'A' AND 'B' TO BE COMPACTED TO A DRY DENSITY OF 100% OF THE MATERIAL'S RESPECTIVE SPMD. THE SUBGRADE TO BE COMPACTED TO 75 MINUS 400 mm WITHIN THE SUBGRADE DENSITY.
3. ROADWAYS TO BE CONSTRUCTED WITH MIN. 450 mm GRANULAR 'B', 150 mm GRANULAR 'A', 80 mm HL8 ASPHALT, AND 40 mm HL8 ASPHALT.
4. JOINTS WITH EXISTING ASPHALT TO BE SAW CUT STRAIGHT PRIOR TO PLACING NEW ASPHALT. WHERE EXISTING ASPHALT IS THICKER THAN 150 mm, IT SHALL BE DEEP LAP JOINT SHALL BE GRIND INTO EXISTING ASPHALT PRIOR TO THE PLACEMENT OF SURFACE COURSE ASPHALT.
5. ALL GRANULAR AND ASPHALT MATERIAL TO BE PLACED IN ACCORDANCE WITH OPSS-MM 310 AND OPSS-MM 314.
6. STOP SIGNS AND STREET SIGNS TO BE INSTALLED PER TOWN STANDARDS AND ONTARIO TRAFFIC MANUAL BOOK 7.
7. CURB TO BE CONSTRUCTED TO BE IN ACCORDANCE WITH OPSS-MM 310.
8. CONCRETE CURB TO OPSS 600.060 AND OPSS 600.110 (AS SPECIFIED) AND OPSS-MM 353.
9. CURB DEPRESSIONS AT SIDEWALK CROSSINGS IN ACCORDANCE WITH OPSS 310.033.
10. CURB DEPRESSIONS AT DRIVEWAYS IN ACCORDANCE WITH OPSS 351.010.
11. CONCRETE DRIVEWAY TO BE CONSTRUCTED IN ACCORDANCE WITH OPSS 608.010.
12. CONCRETE SIDEWALK TO OPSS 310.020, CONCRETE SIDEWALK RAMPS TO OPSS 310.033 AND OPSS 351. SUBBASE TO CONSIST OF 150 mm DEPTH GRANULAR 'A'.
13. UNPAINTED CAST IRON TACTILE WALKING SURFACE INDICATOR COMPONENTS TO BE IN ACCORDANCE WITH OPSS 310.039.
14. ASPHALT DRIVEWAYS TO BE CONSTRUCTED WITH A MINIMUM OF 65 mm OF HL3A ASPHALT AND 200 mm GRANULAR 'A'.
15. GRANULAR TRAILS TO BE CONSTRUCTED WITH 100 mm COMPACTED LIMESTONE SCREENINGS AND 100 mm GRANULAR 'A'. ASPHALT TRAILS TO BE CONSTRUCTED WITH 150 mm GRANULAR 'B', 100 mm GRANULAR 'A' AND 50 mm HL3 SURFACE COURSE ASPHALT.
16. 100 mm DIAMETER PIPE SUBDRAINS SHALL BE PROVIDED ON BOTH SIDES OF THE ROAD IN ACCORDANCE WITH OPSS-MM 405 AND OPSS 216.021, UNWRAPPED TRENCH, GRANULAR 'A' EMBEDED.
17. THE ROADWAY SHALL BE COMPLETELY TO BE BUILT WITHIN THE 2.0 m SECTION IMMEDIATELY UPSTREAM OF ALL STRUCTURES WHICH SHALL BE NON-PERFORATED.

1. STORM MAINTENANCE HOLES AND CATCH BASIN MAINTENANCE HOLES IN ACCORDANCE WITH OPSPD 701.010 and 701.011.
2. MAINTENANCE HOLES TO BE BENCH TO OPSPD 701.021. MINIMUM BENCHING WIDTH SHALL BE 230 mm. CATCH BASIN MAINTENANCE HOLES TO HAVE A SUMP PER OPSPD 701.010.
3. MAINTENANCE HOLE AND CATCH BASIN MAINTENANCE HOLE STEPS TO OPSPD 405.010.
4. MAINTENANCE HOLE FRAMES AND GRATES TO OPSPD 401.010, TYPE "A" CLOSED COVER.
5. CATCH BASINS AND DOUBLE CATCH BASINS TO OPSPD 705.010 AND 705.020 C/W 600 mm SUMP. CATCH BASINS AND DOUBLE CATCH BASINS FRAMES AND GRATES TO OPSPD 400.020. REAR LIFT CATCH BASIN FRAME AND GRATES TO OPSPD 400.020. CATCH BASIN FRAME AND GRATES TO BE CURB LINE TO OPSPD 610.010.
6. DITCH INLETS TO OPSPD 705.030, GRATES INSTALLED IN ACCORDANCE WITH OPSPD 403.010 (4:1 SLOPE UNLESS OTHERWISE SPECIFIED), C/W 600 mm SUMP. REAR LIFT DITCH INLET CATCH BASINS WITHOUT SUMP.
7. CATCH BASIN LEADS - 300 mm DIA. SINGLE AND 300 mm DIA. DOUBLE. CATCH BASIN CONNECTIONS TO OPSPD 708.010 AND OPSPD 708.030.
8. STORM MAINTENANCE HOLES AND CATCH BASIN CONNECTIONS TO TOWN STD. DRAWING ST-STD-SUMP, 100 mm DIAMETER, GRANULAR LAYER 150 mm BEDDING AND 300 mm COVER), USING PREMANUFACTURED CONNECTIONS TO THE MAIN. TERMINATE WHERE SHOWN C/W A CAP/PLUG AND A 38 mm X 89 mm MARKER PLACED FROM THE INVERT TO 600 mm ABOVE FINISHED GRADE PAINTED WHITE. MINIMUM GRATE TO BE 1.0%. TERMINATE AT AN OBVERT ELEVATION AT LEAST 1.4 m BELOW PROPOSED GRADE. BE EXTENDED 5.5 m BEHIND BACK OF CURB.
9. STORM COVERS WITH LESS THAN 1.5 m OF COVER REQUIRE 50 mm OF INSULATION INSTALLED PER THE DETAIL DRAWING.

1. SANITARY MAINTENANCE HOLES TO OPSD 701.010.
2. SANITARY MAINTENANCE HOLES TO BE BENCHMARKED TO OPSD 701.021 ALL CONNECTIONS TO MAINTENANCE HOLES TO INCLUDE A KOR-N-SEAL RUBBER BOOT PIPE CONNECTION.
3. MAINTENANCE HOLE STEPS TO OPSD 405.010.
4. MAINTENANCE HOLE FRAME AND COVER TO OPSD 401.010, TYPE 'A' CLOSED COVER.
5. MAINTENANCE HOLE STRUCTURES EXCEEDING 5.0m IN DEPTH TO INCLUDE SAFETY PLATFORM TO OPSD 404.020.
6. DROP STRUCTURES AT MAINTENANCE HOLES TO OPSD 1003.020.
7. RESIDENTIAL SERVICE CONNECTIONS TO OPSD 1006.010, WITH AN APPROVED MANUFACTURED TEE AT THE MAIN, 125mm DIAMETER MAIN, 150mm MINIMUM SLOPE AND 300 mm COVER.
8. RESIDENTIAL SERVICE CONNECTIONS TO BE TERMINATED 5.5m BEHIND BACK OF CURB WITH PLUG SUITABLY BRACED TO WITHSTAND TEST PRESSURES AND A 38mm x 89mm MARKER PLACED FROM THE INVERT OF THE CONNECTION TO 600 mm ABOVE FINISHED GRADE PAINTED GREEN, MINIMUM GRADE OF SERVICE TO BE 2%, MAXIMUM GRADE TO BE 8% TERMINATE AT AN ELEVATION AT LEAST 2.7m BELOW PROPOSED GRADE AT TERMINATION POINT.
9. MAIN DRAWDINGS BE TO BE SHOWN ALL SEWER CONNECTIONS WHERE THE ANGLE OF CONNECTION BETWEEN THE SERVICE AND SEWER EXCEEDS 90°.

1. ALL WORK ON EXISTING WATERMAIN TO BE COORDINATED WITH THE TOWN.
2. MINIMUM GROUND COVER OVER WATERMAIN, SERVICE LATERALS AND HYDRANT LEADS TO BE 1.7m at ALL POINTS.
3. MAXIMUM GROUND COVER OVER WATERMAIN TO BE 2.5 m.
4. OVERLAPPING OF EXISTING WATERMAIN OR SERVICES WITH LESS THAN 1.7m DEPTH OF COVER AS NOTED ON THE DRAWINGS OR MINIMUM AS FOLLOWS:
- 5.1 DEPTH OF COVER BETWEEN 1.2 TO 1.7m REQUIRES 500mm INSULATION.
- 5.2 DEPTH OF COVER BETWEEN 1.4 TO 1.7m REQUIRES 100mm INSULATION.
- 5.3 WATERMAIN NOT TO BE INSTALLED WITH LESS THAN 1.2 METRE DEPTH OF COVER.
6. THRUST BLOCKS OR PIPE RESTRAINTS TO BE PROVIDED AT ALL CHANGES IN PIPE DIRECTION, TERMINATIONS AND ANY LOCATION WHERE THRUST PRESSURES MAY OCCUR. WATER VALVES SHALL BE RESTRAINED ON EITHER SIDE TO THE VALVE. THE STANDARD MINIMUM THRUST BLOCKS ARE CONCRETE. IN DISTURBED SOILS OR SOILS WITH BEARING STRENGTH OF LESS THAN 200 kPa, PIPE RESTRAINERS SHALL BE USED. IN LIEU OF THRUST BLOCKS PIPE RESTRAINTS FOR PVC SHALL BE PER TOWN STANDARDS, INSTALLED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS. THREADED ROD IN JOINT RESTRAINT IS NOT PERMISSIBLE.
7. CATHODIC PROTECTION OF ALL WATERMAIN FITTINGS AND APPURTENANCES TO BE PROVIDED AS PER TOWN STANDARDS (SEE CHART).
8. RESIDENTIAL SERVICE CONNECTIONS TO OPSD 1104.010, 25 mm DIAMETER, 300 mm DEPTH GRANULAR 'A' EMBEDMENT.
9. SIDE OF ROAD SERVICE CONNECTIONS TO HAVE CURB STOP INSTALLED 2.15m BEHIND BACK OF CURB ON SIDEWALK. SIDE OF ROAD AND 1.8m BEHIND BACK OF CURB ON SIDE OF ROAD WITHOUT SIDEWALK. SERVICE ON HOUSE SIDE OF CURB STOP TO BE EXTENDED 5.5 m BEHIND BACK OF CURB WITH MIN. 1.7m COVER AND 300mm DEPTH EMBEDEMNT. THEN TESTING SHALL BE IN ACCORDANCE TO SURFACE CAPPED OR CRIMPED AND A 35mm x 89mm THREADED ROD FROM SERVICE TO 500 mm ABOVE GRADE PAINTED BLUE. THE TESTING TALL SHALL INCLUDE A MINIMUM 3 m LENGTH OF SERVICE PIPE ABOVE GRADE.
10. HYDRANTS TO BE INSTALLED TO OPSD 1105.010.
11. HYDRANTS TO BE PAINTED CHROME YELLOW AND INCLUDE A FLEXSTEAK HYDRANT MARKER MODEL FH804, 1.2 m LONG. THE CURB STOP SHALL BE CHROME YELLOW ON BOTH SIDES AT THE TOP OF THE MARKER. MARKER TO BE POSITIONED ON THE RIGHT FOOT AS VIEWED FROM THE STREET. A FIRE HYDRANT MARKER STOP AND SIGN SHALL BE INSTALLED 0.3 m BEHIND EACH HYDRANT. THE SIGN SHALL BE REFLECTIVE WITH A RED HYDRANT ON A WHITE BACKGROUND AND A MESSAGE OF 0.3 m BEHIND THE SIGN. THE SIGN SHALL MOUNTED 1.5 m ABOVE GRADE.
12. ALL PVC WATERMAIN AND RESIDENTIAL SERVICES TO HAVE TRACER WIRE BETWEEN HYDRANTS AND OTHER CONDUCTING APPURTENANCES. CONTRACTOR SHALL TEST ALL TRACER WIRE TO CONFIRM CONNECTIVITY.
13. TRACER WIRE TO BE 10 GAUGE, MULTI-STRAND SHALL BE PLACED ON TOP AND ATTACHED IN TWO PLACES ON EACH LENGTH OF CURB STOP OR PE PIPE. ALL CONNECTIONS SHALL BE MADE WITH "DRYCONC WATERPROOF CONNECTORS" OR EQUIVALENT COLD.
14. VERTICAL CLEARANCE BETWEEN WATERMANS AND SEWERS TO BE A MINIMUM OF 0.5m WHEN WATERMAIN IS BELOW THE SEWERS. HORIZONTAL CLEARANCE BETWEEN WATERMANS AND SEWERS TO BE A MINIMUM OF 25mm.
15. THE CONTRACTOR TO PROVIDE DETAILED WRITTEN WATERMAIN COMMISSIONING PROTOCOL FOR APPROVAL PRIOR TO SUPPLY AND INSTALLED BY THE BUILDER DURING HOUSE CONSTRUCTION.
16. THE COMPLETE WATER SYSTEM, INCLUDING RESIDENTIAL SERVICE CONNECTIONS TO THE CURB STOP VALVE AND HYDRANTS SHALL BE TESTED IN ACCORDANCE WITH THE TOWN'S WATERMAIN COMMISSIONING PROTOCOL. THE CONTRACTOR TO PROVIDE DETAILED WRITTEN WATERMAIN COMMISSIONING PROTOCOL FOR APPROVAL PRIOR TO COMMENCING TESTING OPERATIONS. CONNECTIONS TO EXISTING MAINS SHALL NOT BE MADE UNTIL WRITTEN AUTHORIZATION IS PROVIDED BY THE ENGINEER AND THE TOWN.
17. FOLLOWING TESTING, CONTRACTOR SHALL OPERATE EACH SERVICE PIPE TO VERIFY FULL FLOW AND PRESSURE AT CURB STOP.
18. WATER VALVES TO BE OPERATED BY TOWN STAFF ONLY.

1. ALL MATERIAL TO COMPLY WITH CSA, OPSS AND TOWN STANDARDS.
2. SANITARY SEWER - PVC DR 35.
3. SANITARY SERVICE CONNECTIONS - PVC SDR 28.
4. STORM SEWER - PVC SDR 35 OR CONCRETE 85-D. ALL SEWER TO BE JOINED WITH A GASKETED BALL AND SPIGOT SYSTEM. NON-REINFORCED CONCRETE PIPE MAY BE USED FOR SIZES UP TO AND INCLUDING 375 mm DIA.
5. REINFORCED CONCRETE PIPE MAY BE USED FOR ALL SIZES OF SEWER.
6. STORM SERVICE CONNECTIONS - PVC SDR 28, COLOUR WHITE.
7. PERFORMED SUBDRAIN - BIG "O" WITH GEOTEXTILE FILTER SOCK OR APPROVED EQUAL.
8. ALL CHEMICALS AND MATERIALS USED IN THE ALTERATION OR OPERATION OF THE DRINKING WATER SYSTEM THAT COMES IN CONTACT WITH WATER WITHIN THE SYSTEM SHALL MEET ALL APPLICABLE STANDARDS SET BY BOTH THE AMERICAN WATER WORKS ASSOCIATION ("AWWA") AND THE AMERICAN NATIONAL STANDARDS INSTITUTE ("ANSI") SAFETY CRITERIA STANDARDS NSF/60, NSF/61 AND NSF372.
9. WATERMAIN - PVC DR 18.
10. WATER SERVICE CONNECTIONS TO BE 25 mm DIA. TYPE 'K' COPPER PIPE OR REHAU'S MUNICIPLEX (BLUE).
11. POLYETHYLENE MEETING ANSI/AWWA C904.
12. WATER SERVICE FITTINGS SHALL BE:
 - 10.1. MAIN STOP - MUELLER B25008 OR CAMBRIDGE BRASS SERIES 301NL
 - 10.2. CURB STOP - MUELLER B25209 OR CAMBRIDGE BRASS SERIES 202NL
 - 10.3. SERVICE SADDLE - ROBAR 2628 DOUBLE STRAP OR CAMBRIDGE BRASS 8403 DOUBLE BOLT
 - 10.4. TAPPING SLEEVE - ROBAR 6606
 - 10.5. SERVICE BOXES- MUELLER A-726, STAINLESS STEEL RODS
 - 10.6. PIPE RESTRAINTS - SIGMA C-900.
13. HYDRANTS MUELLER CENTURY OR K 2780 SERIES NOSTALGIC STYLE DRY BARREL, OPEN LEFT, WITH STORTZ CONNECTIONS ON ALL STEAMER PORTS. HYDRANT SETS SHALL BE INSTALLED NOT LESS THAN 0.9 m FROM THE CENTER OF THE VALVE TO THE CENTER OF THE HYDRANT. A HYDRANT SIGN AND YELLOW FLEX MARKER SHALL BE INSTALLED 1m BEHIND THE HYDRANT. TRACER WIRE SHALL BE ATTACHED TO THE OUTSIDE OF THE VALVE BOX AND WIRE BROUGHT INTO VALVE BOX UNDER CAP.
14. THE TRACER WIRE SHOULD BE COAXY COATED COMPLETE WITH STAINLESS STEEL BOLTS.
15. MECHANICAL JOINT DUCTILE FITTINGS TO AWWA/ANSI C153/A21.53, INCLUDING PROTECTO-CAPS, CAT NO. 175P190 OR APPROVED EQUAL.
16. ISOLATION VALVES TO BE RESILIENT SEAT GATE VALVES WITH MECHANICAL JOINTS, OPEN COUNTER CLOCKWISE, CLOSURE BY TURNING HANDLE BOXES TO BE BIBBY OR STAR PIPE SLIDE TYPE UPPER AND LOWER MVB COMPOSITE COMPLETE WITH GUIDE PLATE AND DUCTILE ADJUSTABLE TOP AND LID OR APPROVED EQUAL. CAPS TO BE PAINTED BLUE.
17. WATERMAIN FITTINGS TO HAVE ZINC NUTS.
18. ALL SPECIFIED AGGREGATES TO OPS.MUNI 1010.
19. FILTER FABRIC - TERRAFLEX 270R OR APPROVED EQUAL.
20. INSULATION - STYROFOAM HIGLOWAD 40 EXTRUDED POLYSTYRENE FOAM INSULATION, 50mm THICK SHEETS.

WTM/FITTING	ANODE SIZE (kg)	SPACING
100 mm	2.3	PER LENGTH OVER 3.0 m OR FITTING OF SIMILAR SIZE
150 mm	2.3	PER LENGTH OVER 3.0 m OR FITTING OF SIMILAR SIZE
200 mm	5.5	PER LENGTH OVER 3.0 m OR FITTING OF SIMILAR SIZE
250 mm	5.5	PER LENGTH OVER 3.0 m OR FITTING OF SIMILAR SIZE
300 mm	11	PER LENGTH OVER 3.0 m OR FITTING OF SIMILAR SIZE
COPPER SERVICE	2.3	AT EACH CURBSTOP
HYDRANT	5.5	AT HYDRANT BASE
VALVE	5.5	AT EACH VALVE
SERVICE SADDLE	2.3	AT EACH SERVICE SADDLE (CONNECT WIRE TO BOLT ON SADDLE TIGHT BETWEEN 2 NUTS)
TEES, ELBOWS ETC.	2.3	ON EACH FITTING FOR 100 mm – 150 mm PIPE
TEES, ELBOWS ETC.	5.5	ON EACH FITTING FOR 200 mm – 300 mm PIPE

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE
LOCATED AT THE SOUTH WEST CORNER OF GREY
ROAD 19 AND JOZO WEIDER BOULEVARD

Town of Blue Mountains
Planning and Development Services
Accepted For Construction

AFC Drawings are only valid as part and upon execution of a
Development Agreement

Barbara Wood 30 June 2012
signature date

No.	REVISION DESCRIPTION	DATE
1.	1ST SUBMISSION	JUL 4/19
2.	2ND SUBMISSION	NOV 20/19
3.	3RD SUBMISSION	MAR 20/20
4.	4TH SUBMISSION	APR 27/20






**MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS**



DESIGN: DEP/AO	FILE: 117227	DWG: DE-1
DRAWN: DEP	DATE: SEP 2017	
CHECK: DJH	SCALE: AS NOTED	

DETAILS & NOTES

Drawing Name: 117227_DE01.dwg, Plotted: Apr 29, 2020



DISCLAIMER AND COPYRIGHT

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

TATHAM ENGINEERING LIMITED CLAIMS COPYRIGHT TO THIS DRAWING WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF TATHAM ENGINEERING LIMITED.

BENCHMARKS

TBM1 - ELEVATION 226.036
TOP NUT FIRE HYDRANT LOCATED AT THE NORTHWEST CORNER OF MOUNTAIN DRIVE AND JOZO WEIDER BOULEVARD (99-21)

TBM2 - ELEVATION 224.127
RAIL ROAD SPIKE IN WEST FACE OF HYDRO POLE LOCATED AT THE SOUTH WEST CORNER OF GREY ROAD 19 AND JOZO WEIDER BOULEVARD

NOTES



No.	REVISION DESCRIPTION	DATE
1.	3RD SUBMISSION	MAR 20/20
2.	4TH SUBMISSION	APR 27/20
2.	UPDATED PEDESTRIAN GATE DETAIL	MAY 21/20

ENGINEER STAMP



**MANORWOOD HOMES - SECOND NATURE
PHASE 2 BLOCK - 152
TOWN OF THE BLUE MOUNTAINS**





DETAILS

DESIGN: DEP/AO	FILE: 117227	DWG:
DRAWN: DEP	DATE: SEP 2017	
CHECK: DJH	SCALE: AS NOTED	

DE-2

PLANT LIST						
KEY	BOTANICAL NAME	COMMON NAME	SIZE	COND.	SPACING	QTY
Deciduous Trees						
Ac	Amelanchier canadensis	Serviceberry (Multistem)	200 cm	W.B.		14
Af	Acer x freemanii 'Jeffersred'	Autumn Blaze Maple	50mm cal.	W.B.		5
Ar	Acer rubrum 'Karpick'	Karpick Maple	50mm cal.	W.B.		9
As	Acer saccharum	Sugar Maple	50mm cal.	W.B.		4
Al	Amelanchier laevis PP15304	Spring Flurry Serviceberry	50mm cal.	W.B.		6
Ms	Malus 'Sugar Tyme'	Sugar Tyme Crabapple	50mm cal.	W.B.		5
Pc	Pyrus calleryana 'Glen's Form'	Chanticleer Ornamental Pear	50mm cal.	W.B.		5
Qr	Quercus rubra	Red Oak	50mm cal.	W.B.		7
TcH	Tilia cordata 'Halka'	Summer Sprite Linden	50mm cal.	W.B.		3
Coniferous Trees						
Pg	Picea glauca	White Spruce	200cm	W.B.	4m o.c.	23
Ps	Pinus strobus	White Pine	200cm	W.B.	4m o.c.	12
To	Thuja occidentalis 'Emerald'	Emerald Cedar	200cm	W.B.	2.5m o.c.	19
Deciduous Shrubs						
Cs	Cornus stolonifera 'Kelsey'	Kelsey Dogwood	40cm	3 gal.	1.0m o.c.	35
Di	Diervilla lonicera	Bush Honeysuckle	40cm	3 gal.	1.0m o.c.	64
Rt	Rhus typhina	Staghorn Sumac	80cm	3 gal.	1.5m o.c.	9
Perennials & Groundcovers						
ef	Euonymus fortunei 'Coloratus'	Purpleleaf Wintercreeper		1 gal.	0.5m o.c.	67



KEY PLAN

NTS

LEGEND

HYD & WV

●

○

✱

+

✱

SP

QTY

PROPERTY BOUNDARY

LOT BOUNDARY

HYDRO TRANSFORMER - SEE ENG. DWGS

FIRE HYDRANT - SEE ENG. DWGS

SIGN - SEE ENG. DWGS

CATCHBASIN - SEE ENG. DWGS

MANHOLE - SEE ENG. DWGS

LIGHT STANDARD - SEE ENG. DWGS

UNDERGROUND SERVICES - SEE ENG. DWGS

SWALE - SEE ENG. DWGS

SNOW STORAGE - SEE ENG. DWGS

DECIDUOUS TREE

CONIFEROUS TREE

SHRUB GROUPING

MULCHED PLANTING BED - BY OTHERS

PLANT REFERENCE TAG

GENERAL NOTES

1. DEPICTED ON THIS PLAN ARE THE SPECIES AND THE APPROXIMATE LOCATION OF STREET TREES. ONCE DRIVEWAYS, SERVICES, UTILITIES, LIGHT STANDARDS AND OTHER ABOVE AND BELOW GROUND FEATURES ARE INSTALLED, THE EXACT LOCATION OF STREET TREES WILL BE STAKED ON SITE AND APPROVED BY THE LANDSCAPE ARCHITECT AND TOWN PRIOR TO PLANTING.

2. TREE PITS AND PLANTING BEDS FOR ALL TREES AND SHRUBS LOCATED WITHIN 1 METER OF UNDERGROUND UTILITIES OR SERVICES ARE TO BE HAND DUG.

3. ACTUAL LAYOUT OF TREES SHALL BE IN ACCORDANCE WITH THE FOLLOWING 'TABLE OF OFFSETS':

TABLE OF OFFSETS

THE FOLLOWING MINIMUM CLEARANCES FOR TREES SHALL APPLY:

FIRE HYDRANTS	3.0m
DRIVEWAYS	1.5m
NEIGHBOURHOOD MAILBOXES	3.0m
HYDRO TRANSFORMERS	3.0m
BELL OR CABLE PEDESTALS	1.0m
STREETLIGHT POLES	5.0m
UNDERGROUND SERVICES	1.0m
FACE OF ALL WARNING SIGNS	18.0m

4. WHEN THE MINIMUM DISTANCES NOTED IN THE 'TABLE OF OFFSETS' CANNOT BE ACHIEVED, STREET TREES SHALL BE PLANTED IN AN ALTERNATE LOCATION APPROVED OR STIPULATED BY THE TOWN.

5. ALL PLANTING TO BE IN ACCORDANCE WITH NOTES AND DETAILS ON LD-1.

CONTRACT DRAWINGS

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE CONSULTANT BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

ENVISION-TATHAM CLAIMS COPYRIGHT TO THIS DOCUMENT WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE LANDSCAPE ARCHITECT WITHOUT THE EXPRESS CONSENT OF ENVISION-TATHAM

NOTES

1. BASE PLAN PREPARED BY TATHAM ENGINEERING (APRIL, 2020).

2. ALL DIMENSIONS IN METRES UNLESS OTHERWISE NOTED.

1.

NO.

SECON SUBMISSION

APR 27/20

AB

APPROVED

SECOND NATURE

BLOCK 152

TOWN OF THE BLUE MOUNTAINS

PLANTING PLAN

SCALE: 1:250

DESIGN: AB

DRAWN: AJS

CHECKED: AB

DATE: NOV. 21, 2019



JOB NO.

ET115014-2

DWG.

LP-1

115 Sandford Fleming Drive,
Suite 200, Collingwood,
ON L9Y 5A6
Tel. 705.445.0422
inquiry@envision-tatham.com




KEY PLAN NTS

- LEGEND**
- PROPERTY BOUNDARY
 - LOT BOUNDARY
 - HYD TRANSFORMER - SEE ENG. DWGS
 - FIRE HYDRANT - SEE ENG. DWGS
 - SIGN - SEE ENG. DWGS
 - CATCHBASIN - SEE ENG. DWGS
 - MANHOLE - SEE ENG. DWGS
 - LIGHT STANDARD - SEE ENG. DWGS
 - UNDERGROUND SERVICES - SEE ENG. DWGS
 - SWALE - SEE ENG. DWGS
 - SNOW STORAGE - SEE ENG. DWGS
 - BOULEVARD TREE - BY OTHERS
 - DECIDUOUS TREE
 - CONIFEROUS TREE
 - SHRUB GROUPING
 - MULCHED PLANTING BED - BY OTHERS
 - SPECIES QUANTITY
 - PLANT REFERENCE TAG


- NOTES**
- FOR PLANT LIST AND TREE LAYOUT NOTES SEE DRAWING LP-1.
 - FOR PLANTING DETAILS AND NOTES SEE DRAWING LD-1.

Town of Blue Mountains
Planning and Development Services
Accepted For Construction
APC Drawings are only valid as part and upon execution of a Development Agreement
Rosemary Wood 30-June-2020
signature date

CONTRACT DRAWINGS CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE CONSULTANT BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED. ENVISION-TATHAM CLAIMS COPYRIGHT TO THIS DOCUMENT WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE LANDSCAPE ARCHITECT WITHOUT THE EXPRESS CONSENT OF ENVISION-TATHAM	NOTES 1. BASE PLAN PREPARED BY TATHAM ENGINEERING (APRIL, 2020). 2. ALL DIMENSIONS IN METRES UNLESS OTHERWISE NOTED.				APPROVED 	SECOND NATURE BLOCK 152 TOWN OF THE BLUE MOUNTAINS		 ENVISIONTATHAM 115 Sandford Fleming Drive, Suite 200, Collingwood, ON L9Y 5A6 Tel. 705.445.0422 inquiry@envision-tatham.com	
	1. SECOND SUBMISSION APR. 27/20 AB								
	NO. REVISIONS DATE INITIAL					DESIGN: AB	CHECKED: AB	DWG. LP-2	
						DRAWN: AJS	DATE: NOV. 21, 2019		




- NOTES**
1. ALL MATERIALS ARE SPECIFIED IN THE GENERAL PLANTING NOTES.
 2. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.
 3. POSITION CROWN OF ROOT BALL 75mm ABOVE FINISHED GRADE TO ALLOW FOR SETTLING.
 4. CORRECTIVE PRUNE TO RETAIN NATURAL FORM OF TREE AS DIRECTED BY THE LANDSCAPE ARCHITECT, INCLUDING REMOVAL OF DEAD, BROKEN, OR CROSSING BRANCHES. DO NOT REMOVE MORE THAN 20% OF LIVE CANOPY.
 5. FOR TREES PLANTED WITHIN PLANTING OR SHRUB BEDS, DELETE SAUCER AROUND BASE OF TREE.
 6. NO TREE PITS SHALL BE LEFT OPEN OVERNIGHT.
 7. STAKES AND TIES TO BE REMOVED ONE YEAR AFTER PLANTING.



- NOTES**
1. ALL MATERIALS ARE AS SPECIFIED IN THE GENERAL PLANTING NOTES.
 2. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.
 3. POSITION CROWN OF ROOT BALL 75mm ABOVE FINISHED GRADE TO ALLOW FOR SETTLING.
 4. CORRECTIVELY PRUNE TREES AS DIRECTED BY THE LANDSCAPE ARCHITECT, INCLUDING REMOVAL OF DEAD OR BROKEN BRANCHES. DO NOT REMOVE MORE THAN 20% OF LIVE CANOPY. PRUNING TO BE UNDERTAKEN BY ISA CERTIFIED ARBORIST.
 5. FOR TREES PLANTED WITHIN PLANTING OR SHRUB BEDS, DELETE SAUCER AROUND BASE OF TREE.
 6. NO TREE PITS SHALL BE LEFT OPEN OVERNIGHT.
 7. REMOVE STAKES AND TIES ONE YEAR AFTER PLANTING.

- NOTES**
1. ALL MATERIALS ARE SPECIFIED IN THE GENERAL PLANTING NOTES.
 2. FOR SHRUBS PLANTED IN SHRUB BEDS, DELETE SAUCER AROUND BASE OF SHRUB.
 3. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.
 4. POSITION CROWN OF ROOT BALL 25mm ABOVE FINISH GRADE TO ALLOW FOR SETTLING.



GENERAL NOTES

1.0 PLANTING

1. SUPPLY AND INSTALL TREES, SHRUBS AND GROUNDCOVERS IN ACCORDANCE WITH THE APPLICABLE DETAILS AND SPECIFICATIONS.
2. PLANT MATERIAL SHALL BE IN ACCORDANCE WITH THE CANADIAN LANDSCAPE STANDARD (LATEST EDITION), PUBLISHED BY THE CANADIAN NURSERY LANDSCAPE ASSOCIATION AND THE CANADIAN SOCIETY OF LANDSCAPE ARCHITECTS, EXCEPT WHERE SPECIFIED OTHERWISE.
3. ALL PLANTS SHALL BE SUPPLIED AS SPECIFIED IN THE "PLANT LIST". SUBSTITUTIONS WILL NOT BE ACCEPTED UNLESS APPROVED IN WRITING BY THE LANDSCAPE ARCHITECT.
4. ALL MATERIALS TO BE APPROVED BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
5. **MULCH** TO BE SHREDDED CEDAR BARK FREE OF DYES AND CHEMICALS, OR APPROVED EQUAL.
6. **PLANTING SOIL MIXTURE** SHALL BE TWO PARTS SCREENED TOPSOIL TO ONE PART SCREENED COMPOST WITH BONEMEAL APPLIED AT A RATE OF 0.6KG PER CUBIC METRE, AS SPECIFIED. CONTRACTOR SHALL PROVIDE SOURCE AND SAMPLE OF SOIL MIXTURE, AS SPECIFIED, FOR APPROVAL PRIOR TO COMMENCING WORK.
7. **TREE STAKES** TO BE 1800mm LONG HEAVY DUTY GAUGE "T-BARS".
8. **TIES** SHALL BE WOVEN POLYPROPYLENE PROPRIETARY TIE SYSTEMS THAT REMAIN FLEXIBLE DURING WINTER MONTHS. 50mm WIDE BURLAP STRIPS LOOPED IN A LOOSE FIGURE 8 AND SECURED WITH WIRE TIES ARE ALSO ACCEPTABLE.
9. **TRUNK PROTECTION** TO BE 100mm DIA. HDPE PIPE, 500mm LONG OR TO LOWEST BRANCH, EXCEPT IN SWM PONDS AND NATURALIZATION AREAS WHERE IT IS TO BE WHITE SPIRAL PLASTIC TREE GUARD.
10. STAKES AND TIES SHALL BE REMOVED 1 YEAR AFTER PLANTING.
11. TRUNK PROTECTION SHALL BE REMOVED AT COMPLETION OF WARRANTY PERIOD.
12. CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND OFFSITE DISPOSAL OF EXCAVATED MATERIAL FROM PLANTING BED CONSTRUCTION AND TREE PIT EXCAVATION.

2.0 TOPSOIL & FINISH GRADING

1. ALL TOPSOIL AND FINISH GRADING SHALL BE IN ACCORDANCE WITH OPSS 802, UNLESS OTHERWISE SPECIFIED.
2. SUPPLY, PLACE, FINE GRADE, AND COMPACT SPECIFIED DEPTH OF IMPORTED SCREENED TOPSOIL MEETING THE SPECIFICATIONS FOR "TOPSOIL" FOR ALL DISTURBED AREAS.
3. TOPSOIL SHALL BE IMPORTED TOPSOIL, PROVIDE SOURCE AND SAMPLE FOR APPROVAL BY CONSULTANT PRIOR TO THE SUPPLY, HAULING OR PLACEMENT. THE APPROVED SOURCE MUST NOT BE CHANGED WITHOUT FURTHER APPROVAL BY THE CONSULTANT.
4. TOPSOIL SHALL BE FRIABLE LOAM, NEITHER HEAVY CLAY NOR MATERIAL OF A VERY LIGHT SANDY NATURE, CONTAINING MINIMUM OF 4% ORGANIC MATTER FOR CLAY LOAMS AND 2% FOR SANDY LOAMS, TO MAXIMUM OF 25% BY VOLUME. TOPSOIL SHALL BE FREE OF SUBSOIL, CLAY LUMPS, ROOTS OVER 25 mm IN DIAMETER, GRASS, TOXIC MATERIALS, STONES, OR FOREIGN OBJECTS, HAVING AN ACIDITY RANGE (PH) OF 5.5 - 7.5 AND BE REASONABLY FREE OF WEEDS. TOPSOIL CONTAINING CRABGRASS, CLOVERGRASS, OR OTHER NOXIOUS WEEDS IS NOT ACCEPTABLE. TOPSOIL SHALL BE FRIABLE WHEN MOIST.
5. SCHEDULE PLACING OF TOPSOIL MIXTURE AND FINISH GRADING TO PERMIT SOD AND SEEDING OPERATIONS UNDER OPTIMUM GROWING CONDITIONS.
6. NO WORK SHALL PROCEED IF THE SITE AND SOIL MATERIALS ARE EXCESSIVELY WET.
7. TOPSOIL SHALL BE SPREAD TO A MINIMUM UNIFORM DEPTH OF 150mm FOR ALL GENERAL LANDSCAPE AREAS AND BE 15mm BELOW FINISHED GRADE FOR AREAS TO BE SODDED.
8. ROLL AND COMPACT TOPSOIL TO BETWEEN 83 AND 87% SPMD, UNLESS OTHERWISE INDICATED.
9. TOLERANCES: ALL TOPSOIL FINISH GRADE SURFACES SHALL ON COMPLETION BE SHAPED TO THE GRADES AND CROSS SECTIONS SPECIFIED WITHIN THE FOLLOWING VERTICAL TOLERANCES OF ESTABLISHED GRADE OVER A 3.0m STRAIGHTEDGE (NOT BE UNIFORMLY HIGH OR LOW):
 1. GENERAL LANDSCAPE AREAS, EMBANKMENTS, DITCHES AND SWALES: +/-25mm
 2. SPORTS FIELDS - BASEBALL DIAMOND OUTFIELD: +/-10mm
10. GRADE TO ELIMINATE ROUGH SPOTS, LOW AND UNEVEN AREAS, AND ENSURE SMOOTH TRANSITIONS AND POSITIVE DRAINAGE. PREPARE LOOSE FRIABLE BED BY MEANS OF CULTIVATION AND SUBSEQUENT RAKING.
11. LEAVE SURFACES SMOOTH, UNIFORM, AND FIRM AGAINST FOOTPRINTS, WITH A FINE, LOOSE TEXTURE BEFORE SOD IS PLACED.
12. SURPLUS/ UNSUITABLE OR CONTAMINATED TOPSOIL OR DELETERIOUS MATERIAL SHALL BE DISPOSED OFF-SITE IN LOCATION APPROVED BY THE CONSULTANT.

3.0 SODDING

1. SODDING SHALL BE IN ACCORDANCE WITH OPSS 803, UNLESS OTHERWISE SPECIFIED.
2. SOD SHALL BE NUMBER ONE GRADE TURFGRASS NURSERY SOD WITH A KENTUCKY BLUEGRASS SOD CLASSIFICATION.
3. SOD SHALL BE GROWN AND SOLD IN ACCORDANCE WITH THE "SPECIFICATIONS FOR TURFGRASS SOD FOR ONTARIO" PUBLISHED BY THE NURSERY SOD GROWERS ASSOCIATION (N.S.G.A.) AND SHALL BE ESPECIALLY SOWN AND CULTIVATED IN NURSERY FIELDS AS TURFGRASS CROP.
4. SODDING MAY BE PERFORMED AT ANY TIME BETWEEN MAY 1ST AND NOVEMBER 15TH.
5. SOD SHALL BE DELIVERED TO SITE WITHIN 24 HOURS OF BEING LIFTED IN COMPLETE ROLLS. SMALL IRREGULAR OR BROKEN PIECES OF SOD WILL NOT BE ACCEPTED.
6. LAY SOD WITHIN 36 HOURS OF BEING LIFTED OR WITHIN 24 HOURS OF BEING LIFTED IF AIR TEMPERATURE EXCEEDS 20°.
7. DURING WET WEATHER ALLOW SOD TO DRY SUFFICIENTLY TO PREVENT TEARING DURING LIFTING AND HANDLING.
8. DURING DRY WEATHER, PROTECT SOD FROM DRYING OUT AND WATER SOD AS NECESSARY TO ENSURE ITS VITALITY AND PREVENT DROPPING OF SOIL IN HANDLING. DRY SOD WILL BE REJECTED.
9. LAY SOD SECTIONS IN ROWS WITH JOINTS STAGGERED, BUT SECTIONS CLOSELY WITHOUT OVERLAPPING OR LEAVING GAPS OR OPEN JOINTS BETWEEN SECTIONS. CUT OUT IRREGULAR OR THIN SECTIONS WITH SHARP IMPLEMENTS.
10. ENSURE FINISHED SOD SURFACE IS FLUSH WITH ADJOINING GRASS AREAS, PAVEMENT OR TOP SURFACE OF CURBS.
11. LAY SOD SECTIONS LONGITUDINALLY ALONG CONTOURS OF SLOPES AND START LAYING SOD AT BOTTOM OF SLOPES.
12. PEG SOD ON SLOPES STEEPER THAN 4 HORIZONTAL TO 1 VERTICAL, 100mm BELOW TOP EDGE AT 200mm ON CENTRE FOR FIRST SOD SECTIONS ALONG CONTOURS OF SLOPES AND NOT LESS THAN 4 PEGS PER SQUARE METRE WITH PEGS DRIVEN TO 50 MM ABOVE SOIL SURFACE OF SOD SECTIONS.
13. SOD STAKING SHALL BE WITH WOODEN PEGS AT 17 X 8 X 200mm, OR APPROVED EQUAL.
14. WATER SOD IMMEDIATELY AFTER LAYING TO OBTAIN MOISTURE PENETRATION INTO TOP 100mm OF TOPSOIL.
15. PROVIDE CLOSE CONTACT BETWEEN THE SOD AND THE UNDERLYING ROOT ZONE MIX BY ROLLING WITH A LIGHT ROLLER. IMPERFECTIONS IN THE SURFACE LEVEL SHOULD BE CORRECTED PRIOR TO THE LAYING OF THE SOD AND NOT BY ROLLING WITH A HEAVY ROLLER. USE OF HEAVY ROLLER TO CORRECT IRREGULARITIES TO GRADE IS NOT PERMITTED.
16. MAINTENANCE DURING THE ESTABLISHMENT PERIOD SHALL CONSIST OF BUT NOT BE LIMITED TO WATERING IN SUFFICIENT QUANTITIES AND AT REQUIRED FREQUENCY TO MAINTAIN CONTINUOUS SUBSOIL MOISTURE IMMEDIATELY UNDER SOD TO A DEPTH OF 75-100mm, ROLLING TO REMOVE MINOR DEPRESSIONS OR IRREGULARITIES, WEED CONTROL TO ENSURE THAT NON-SPECIFIED VEGETATION SHALL NOT EXCEED 5%, AND MOWING AT LEAST TWICE TO MAINTAIN GRASS AT A 40mm HEIGHT (AFTER GRASS REACHED 60mm HEIGHT).
17. REMOVE WOODEN SOD PEGS AFTER SOD HAS ESTABLISHED WITH APPROVAL OF THE CONSULTANT.

1 DECIDUOUS TREE PLANTING



NTS

2 CONIFEROUS TREE PLANTING


NTS

3 SHRUB PLANTING

NTS



- NOTES**
1. ALL MATERIALS ARE SPECIFIED IN THE GENERAL PLANTING NOTES.
 2. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.
 3. ENSURE SOIL SETTLEMENT HAS OCCURRED PRIOR TO MULCHING.
 4. PLANTING SOIL DEPTH MAY BE 300mm (MIN.) UNDER PERENNIALS.
 5. CONTRACTOR IS RESPONSIBLE FOR REMOVAL AND OFFSITE DISPOSAL OF EXCAVATED MATERIAL FROM PLANTING BED CONSTRUCTION.



- NOTES**
1. ALL MATERIALS ARE SPECIFIED IN GENERAL PLANTING NOTES.
 2. DO NOT ALLOW AIR POCKETS WHEN BACKFILLING.

4 MULCHED PLANTING BED

NTS

5 CONTINUOUS MULCHED UNDERSTOREY

NTS

CONTRACT DRAWINGS

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE CONSULTANT BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

ENVISION-TATHAM CLAIMS COPYRIGHT TO THIS DOCUMENT WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE LANDSCAPE ARCHITECT WITHOUT THE EXPRESS CONSENT OF ENVISION-TATHAM

- NOTES**
1. ALL DIMENSIONS IN MILLIMETERS UNLESS OTHERWISE INDICATED.

1.	SECOND SUBMISSION	APR. 27/20	AB	
NO.	REVISIONS	DATE	INITIAL	

APPROVED



**SECOND NATURE
BLOCK 152
TOWN OF THE BLUE MOUNTAINS**

LANDSCAPE DETAILS

ENVISIONTATHAM

115 Sandford Fleming Drive,
Suite 200, Collingwood,
ON L9Y 5A6
Tel. 705.445.0422
inquiry@envision-tatham.com

SCALE: AS SHOWN	JOB NO. ET115014-2
DESIGN: AB	CHECKED: AB
DRAWN: AJS	DATE: NOV. 21, 2019
DWG. LD-1	

