



NOTES

1. TOPSOIL TO BE REMOVED TO ITS FULL DEPTH ALONG ENTIRE WIDTH OF ROAD ALLOWANCE BY CONTRACTOR.
2. BOULEVARD – 300mm TOPSOIL AND SOD.
3. DEPTH FOR ALL UTILITIES 0.9m MIN.
4. SIDEWALKS TO OPD 310.010, COMPLETE WITH 150mm GRANULAR 'A' BASE.
5. SIDEWALK, STREET LIGHTS AND TRANSFORMERS ONE SIDE ONLY.
6. CONCRETE BARRIER CURB TO OPD 600.040 (TYP)
7. OUTLET TO CATCH BASINS AS PER OPD 216.021.

CONTRACT DRAWINGS

CONTRACTOR MUST VERIFY ALL DIMENSIONS AND BE RESPONSIBLE FOR SAME. ANY DISCREPANCIES MUST BE REPORTED TO THE ENGINEER BEFORE COMMENCING WORK. DRAWINGS ARE NOT TO BE SCALED.

C.C. TATHAM & ASSOCIATES LTD. CLAIMS COPYRIGHT TO THIS DOCUMENT WHICH MAY NOT BE USED FOR ANY PURPOSE OTHER THAN THAT PROVIDED IN THE CONTRACT BETWEEN THE OWNER/CLIENT AND THE ENGINEER WITHOUT THE EXPRESS CONSENT OF C.C. TATHAM & ASSOCIATES LTD.

PRELIMINARY



C.C. Tatham & Associates Ltd.
Consulting Engineers
Collingwood Braesbridge Ovilla Barrie Orlino

CAMPERDOWN CONDOMINIUMS
TOWN OF THE BLUE MOUNTAINS
TYPICAL CROSS-SECTION
ON 14.0m R.O.W

DWG. No.

DE-2

SCALE: 1:50

DRAWN: RD

DATE: NOV/18

JOB NO. 117304