- ALL SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION AND SHALL REMAIN IN PLACE UNTIL ALL DISTURBED AREAS HAVE BEEN STABILIZED. SEDIMENT AND EROSION CONTROL MEASURES THAT ARE
- THE CONTRACTOR MAY CONSIDER ALTERNATIVE SEDIMENT AND EROSION CONTROL
- EXTREME RAINFALL EVENTS, ETC.

- BLOW-OUTS AND ACCUMULATION OF SEDIMENT.
- DIRECTED BY SITE ENGINEER.
- DIRECTED BY THE SITE ENGINEER.





Project	This Drawing is For	DATE: YYYY/MM/DD	ISSUE	NO.
TOWN OF T	INFORMATION	2023/02/21	ISSUED FOR TREE CLEARING APPLICATION	0
TREE MA	This Drawing should not be redistributed beyond the intended recipient			
			I	





AFC Drawings are only valid as part and upon execution

HOME FARM THE BLUE MOUNTAINS			OZIER TING ENGINEERS
IANAGEMENT PLAN	Drawn By K.C.	Design By K.M.	Project 721-3464
	Check By K.M.	Check By	Drawing TMP-1



1. INSTALL TREE PROTECTION FENCING IN LOCATIONS INDICATED IN CONTRACT DRAWINGS.

2. WHERE POSSIBLE, TREE PROTECTION FENCING LOCATION TO BE AT OR OUTSIDE THE DRIPLINE OF PROTECTED TREES, WHICH IS DEFINED AS THE CIRCLE THAT COULD BE DRAWN ON THE SOIL AROUND A TREE DIRECTLY UNDER THE TIPS OF ITS OUTERMOST AND WIDEST BRANCHES.

3. LOCATION OF TREE PROTECTION FENCE SHALL BE CONFIRMED ON-SITE BY THE LANDSCAPE ARCHITECT BEFORE COMMENCEMENT OF TREE CLEARING

4. TREE CUTTING WILL BE ABOVE GROUND AND THE STUMPS WILL REMAIN UNTIL SUCH TIME AS SITE ALTERATION PERMIT IS ISSUED.

5. THE ROOT SYSTEMS FROM ALL EXISTING VEGETATION TO BE RETAINED SHALL BE PROTECTED FROM DAMAGE, COMPACTION AND CONTAMINATION RESULTING FROM CONSTRUCTION.

6. NO STORAGE OF MATERIALS OR EQUIPMENT WITHIN THE TREE PROTECTION ZONE IS PERMITTED. NO EQUIPMENT OR MATERIALS SHALL HIT OR DAMAGE TREES DESIGNATED TO BE PRESERVED.

7. NO ROOT CUTTING OR MOVEMENT OF VEHICLES IS PERMITTED IN THE TREE PROTECTION ZONE.

8. FENCE BARRIERS MUST REMAIN IN FUNCTIONAL CONDITION UNTIL ALL SITE WORKS INCLUDING LANDSCAPING ARE COMPLETED.

9. THE CONTRACTOR SHALL REMOVE TREE PROTECTION FENCING AFTER THE COMPLETION OF ALL SITE WORKS FOLLOWING WRITTEN APPROVAL BY THE LANDSCAPE

2.0 HAZARD TREE MANAGEMENT

1. SELECTIVE REMOVAL OF HAZARDOUS TREES WITHIN THE TREE PROTECTION ZONE WILL BE DETERMINED ON-SITE BY THE LANDSCAPE ARCHITECT.

2. WHERE REMOVALS ARE REQUIRED, THE FELLING ZONE SHOULD ALLOW THE TREES TO FALL WITHOUT DAMAGE TO EXISTING STRUCTURES, OR TREES (BRANCHES & TRUNKS) TO REMAIN.

3. SHOULD NO CLEAR FELLING ZONE EXIST, THE TREE SHALL BE CUT INCREMENTALLY FROM TOP TO BOTTOM AND LOWERED TO THE GROUND WITH ROPES. 4. ANY ROOTS THAT BECOME EXPOSED DURING

NTS



Nottawasaga Valley					APR'D:	1
Conservation Authority					DRAWN: A.S.C	
TYPICAL DETAIL OF						1
SILT/SEDIMENT FENCE	NO.	REVISION	APR'D	DATE	BSD-23	

2 HEAVY-DUTY SILT FENCE

 NO. 0	ISSUE ISSUED FOR TREE CLEARING APPLICATION	DATE: YYYY/MM/DD	This Drawing is For INFORMATION ONLY This Drawing should not be	Project T C Drawing	
			This Drawing should not be redistributed beyond the intended recipient		

POST NCE NATIVE SOIL TION OF FLOW
DATE 03.03.06 BECALE: NTS

NTS



No grubbing or grading Permitted AFC Drawings are only valid as part and upon execution of a Development Agreement

March, 22-2023 signature date

LD-1



K.M.

Check By

HOME FARM THE BLUE MOUNTAINS

SCAPE DETAILS