



**NOTES**

1. MUD MATS ARE TO BE INSTALLED AND MAINTAINED AS PER SITE CONDITIONS TO ENSURE THERE IS NO MUD TRACKING ON MUNICIPAL ROADS.
2. MUD MAT BE A MINIMUM OF 35m LONG FROM THE PROPERTY LINE, A MINIMUM OF 7m WIDE, AND 0.45m IN DEPTH FILLED WITH CLEAR STONE, GRANULAR 'A' AND 150mm RIP RAP.
3. A MUD SHALL BE PROVIDED AT EVERY ENTRANCE AND START IMMEDIATELY FROM THE BACK OF CURB.
4. CONTRACTOR IS RESPONSIBLE FOR ENSURING SIDEWALK IS SAFE AND MAINTAINED IN GOOD CONDITION.
5. ANY DISTURBANCE / DAMAGE TO THE BOULEVARD IS TO BE REINSTATED TO ITS ORIGINAL CONDITION OR TO SATISFACTION OF THE TOWN.
6. CONTRACTOR SHALL REMOVE ACCUMULATED SEDIMENTS AND DEBRIS AS REQUIRED.
7. THIS DETAIL IS FOR SCHEMATIC INFORMATION ONLY. THE ACTUAL CONFIGURATION USED MUST SATISFY THE INTENT OF THIS DRAWING.



**Town Of The Blue Mountains Standard Drawings**

**MUD MAT DETAIL**

<b>Date</b>	JAN 2023	<b>Scale</b>	N.T.S.	<b>TOTBM STD.</b>	4.14.3
-------------	----------	--------------	--------	-------------------	--------